

CITY OF WESLACO

**A REGULAR MEETING OF THE
PLANNING & ZONING
COMMISSION**

FEBRUARY 3, 2021, 5:30 P.M.

**LEGISLATIVE CHAMBERS AND
VIA ZOOM**

255 S. KANSAS AVENUE

David Hernandez, Chairman
Lonnie Berry, Vice-Chairman
Miles Bullion, PZ Commissioner
Randy Summers, PZ Commissioner
Adrian Torres, PZ Commissioner
Jose Treviño, PZ Commissioner
Jim Forward, PZ Commissioner

**CITY OF WESLACO
PLANNING & ZONING COMMISSION
REGULAR MEETING
JANUARY 6, 2021**

On Wednesday, January 6, 2021, at 5:30 pm., the Planning and Zoning Commission of the City of Weslaco, Texas, convened in regular session in person

The following commissioners were present:

David Hernandez	Chairman
Lonnie Berry	Vice-Chairman
Randy Summers	Commissioner
Jim Forward	Commissioner
Miles Bullion	Commissioner
Jose Treviño	Commissioner
Adrian Torres	Commissioner
Rebekah de la Fuente	Planning Director
Kayla A. Arevalo	Planning Secretary

Also present were; Mike Swinnea, Assistant Fire Marshall; Peter Hermida, Engineering Technician III;; Rolando Gonzalez, building official; and citizens.

I. CALL TO ORDER:

Chairman Hernandez called the meeting to order and welcomed everyone in the audience.

A. Roll Call/Establish a Quorum

Ms. de la Fuente called the roll call noting that, everyone was present at the time of roll, a quorum was established.

II. PUBLIC COMMENTS

There were no comments received.

III. APPROVAL OF MINUTES

A. December 2, 2020 Regular Meeting

Commissioner Summers made a motion to approve the minutes of December 2, 2020, seconded by Commissioner Bullion. Motion carried.

IV. PUBLIC HEARING

A. Discussion and consideration to approve rezone 1630 Canyon Drive. Also being, Lot 171, Westgate Village Ph II, Hidalgo County, Texas from M-1

**Mobile home subdivision district to a B-1 Neighborhood Business district.
Possible Action.**

Ms. de la Fuente stated that notice appeared in The Monitor on December 14, 2020, there were Fourteen (14) property owners notified within the 200-foot radius, no letters for or against the item were received. Staff recommended approval based on surrounding land use.

Commissioner Forward made a motion to close the Public Hearing, seconded by Commissioner Berry. Motion carried.

Commissioner Berry made a motion approve the rezone request, seconded by Commissioner Bullion. Motion carried.

B. Discussion and consideration to approve rezone 515 S. Airport Drive. Also being 18.680 acres out of Farm Tract 21 & 22, West Tract Subdivision and out of an abandoned canal R.O.W., Hidalgo County, Texas from R-1 One-family dwelling district to I Industrial district. Possible Action.

Ms. de la Fuente stated that notice appeared in The Monitor on December 14, 2020, there were Thirty-two (32) property owners notified within the 200-foot radius, no letters for or against the item were received. Staff recommended approval based on surrounding land use.

Commissioner Forward made a motion to close the Public Hearing, seconded by Commissioner Summers. Motion carried.

Commissioner Torres made a motion to approve the rezone request, seconded by Commissioner Summers. Motion carried.

C. Discussion consideration to approve Conditional Use Permit to obtain a Mixed Beverage Permit, Mixed Beverage Late Hours Permit and Beverage Cartage Permit at 260 S. Texas Blvd. Suite 105, Also being a 98'x90' Tract, Block 18, Original Townsite of Weslaco, Weslaco, Hidalgo County, and Texas. Possible Action.

Ms. de la Fuente stated that notice appeared in The Monitor on December 14, 2020, there were Twenty-two (22) property owners notified within the 200-foot radius, no letters for or against the item were received. Staff recommended approval.

Commissioner Berry made a motion to close the Public Hearing, seconded by Commissioner Bullion. Motion carried.

Commissioner Berry made a motion to approve the Conditional Use permit, with the stipulation that one (1) security be on duty during late hours, seconded by Commissioner Treviño. Motion carried.

V. DISCUSSION AND CONSIDERATION

A. Discussion and consideration for Final Plat the Sierra Estates – being 25.00 acre of lot 15 &16 Block 147, West Tract Subdivision, Weslaco, Hidalgo County, Texas located approximately the northwest corner of Mile 4 West and Mile 12 North. Possible Action.

Ms. de la Fuente stated that this item is a twenty (20) lot subdivision is outside the City of Weslaco. This subdivision is being serviced with water by the North Alamo Water Supply Company through an 8” waterline and sewer by OSSF. The property is within a Flood Zone “X”. Applicant was granted a variance for OSSF. Staff recommended approval of the Final plat.

Commissioner Summers made the motion to approve the Final plat, seconded by Commissioner Berry. Motion carried.

B. Discussion and consideration for the Final Plat for Emily Villarreal Subdivision – being 4.00 acre out of Farm Tract 711, West Tract Subdivision, Weslaco, Hidalgo County, Texas located approximately the northeast corner of Mile 5 North Rd and Midway Rd. Possible Action.

Ms. de la Fuente stated that this item is a three (3) lot subdivision is outside the City of Weslaco. This subdivision is being serviced with water by the City of Weslaco through a 6” waterline and sewer by OSSF. The property is within a Flood Zone “B”. Applicant was granted a variance for OSSF. Staff recommended approval of the Final plat.

Commissioner Summers made the motion to approve the Final plat, seconded by Commissioner Buillion. Motion carried.

C. Discussion and consideration for a six-month extension for the Final Plat for San Jacinto Estates No10. Phase II Subdivision – being 13.49-acre tract of land out of Farm Tract 94, West & Adams Tract Subdivision, Hidalgo County, Texas. Approximately on the Northwest corner of Mile 10 North Road and Mile 4 West Road. Possible Action.

Ms. de la Fuente stated that this item is a forty-eight (48) lot subdivision is outside the City of Weslaco. Final Plat approval is set to expire on January 21, 2021. Notice to proceed has been issued for the development and is currently under construction. Staff recommends approval of six-month extension.

Commissioner Summers made the motion to approve the six-month extension, seconded by Commissioner Forward. Motion carried.

D. Discussion and consideration for a six-month extension for the Final Plat for San Pedro Estates Subdivision – being 20 acre tract of land out of Farm Tract 647, West & Adams Tract Subdivision, Hidalgo County, Texas. Approximately 2,964 ft. North of the Intersection of 18th and Milanos Rd. Possible Action.

Ms. de la Fuente stated that this item is a sixteen (16) lot subdivision outside the City of Weslaco city limits. Final Plat approval is set to expire on January 21, 2021. Notice to proceed has been issued for this development and is currently under construction.. Staff recommends approval of six-month extension.

Commissioner Summers made the motion to approve the six-month extension, seconded by Commissioner Berry. Motion carried.

VI. ADJOURNMENT

There being no further business to come before the Planning and Zoning Commission, Chairman Hernandez adjourned the meeting at 5:48 p.m.

Planning and Zoning Commission

David Hernandez, Chairman

Lonnie Berry, Vice-Chairman

Randy Summers, Commissioner

Miles Bullion, Commissioner

Jose Treviño, Commissioner

Adrian Torres, Commissioner

Jim Forward, Commissioner

ATTEST:

Kayla A. Arevalo, Planning Secretary



Planning & Zoning Commission Standardized Agenda Request Form

Date of Meeting: February 3, 2021	Agenda Item No. (to be assigned by PCE): IV. A.
From: Rebekah de la Fuente, Planning Director, on behalf of Ezequiel Reyna Jr.	
Subject/Agenda Item: Discussion and consideration to approve rezone 3701 S. Westgate. Also being West Tract S330' & E440'-S495'-N990'FT 795 15 AC GR 14.77 AC NET, Hidalgo County, and Texas from R-2 Duplex and apartment district.to M-1 Mobile home subdivision district.	
Discussion/Overview: The applicant is requesting to rezone property from R-2 Duplex and apartment district.to M-1 Mobile home subdivision district. Notice of the application and the Public Hearing for the Planning and Zoning Commission appeared in The Monitor on July 3, 2020. Forty-one (41) property owners within 200 feet of the applicant's property were notified by letter on July 10, 2020.	
Staff recommendation for Commission's Action: Staff recommends denial based on surrounding land use and 2040 land use map.	
Additional Action Prompted: ☒ Mayor's Signature ☒ Public Hearing ☐ Budget Amendment ☐ Resolution ☒ Ordinance – First Reading ☒ Ordinance – Final Reading	
Advisory Review, (if any): (name of board/committee, date of action, recommendation): N/A	
If item previously considered, provide date and action by Commission: N/A	
Attachments,(if any): Application for Rezone with attachments.	
Responsibilities upon Commission's Action: Planning staff will advise applicant.	



APPLICATION FOR REZONING

The Planning & Zoning Commission meets every 1st Wednesday of each month at 5:30 pm.
The City Commission meets every 1st and 3rd Tuesday of each month at 5:30 pm

FILE NO. _____

PROPOSED PROJECT

Legal Description of Property to be rezoned:

Lot West Tracts 330 & 440 - 8495 N 990 FT 795.15 AC Block _____

Subdivision Name GR 1477 AC Net

Street Address S. Westgate Dr. 3701 S Westgate Dr.

Existing Zoning R2-multh Existing Land Use _____

Proposed Zoning M1 Proposed Land Use _____

- _____ \$305.00 non-refundable filing fee.
- _____ Detailed dimensioned site plan/map must be submitted with this request.
- _____ Survey and metes and bounds if the legal description is a portion of a lot.
- _____ City and school tax receipts attached.
- _____ I have received a copy of "The Intent of Zoning Application Instructions".

APPLICANT

Name Ezequiel Reyna Jr. Phone (956) 908-2829

Address 702 W. Expressway 83 Fax: (956) 909-9034

City Weslaco State TX Zip Code 78599 E-Mail: Senia.reynaprop@gmail.com

OWNER

Name Ezequiel Reyna Jr. Phone (956) 908-2829

Address 702 W. Expressway 83 Fax: (956) 909-9034

City Weslaco State TX Zip Code 78599 E-Mail: Senia.reynaprop@gmail.com

I certify that I am the actual owner of the property described above and this application is being submitted with my consent (include corporate name if applicable); or I am authorized by the actual owner to submit this application and have attached written evidence of such authorization.

Signature _____ Date 1/8/21


Owner

Signature _____ Date _____

Applicant

Signature _____ Date _____

Authorized Agent



City of Weslaco

"The City on the Grow"



David Suarez, Mayor
Leo Muñoz, Mayor Pro-Tem, District 1
Greg Kerr, Commissioner, District 2
Jose "J.P." Rodriguez, Commissioner, District 3
Adrian Farias, Commissioner, District 4
Letty Lopez, Commissioner, District 5
Josh Pedraza, Commissioner, District 6

Mike R. Perez, City Manager

PLANNING DEPARTMENT

January 22, 2021

Legal Notice

Dear Occupant:

The Weslaco Planning and Zoning Commission will hold a public hearing on Wednesday, February 3, 2021, and the City Commission will hold a public hearing on February 16, 2021 at 5:30 p.m. at the City Hall Legislative Chambers located at 255 South Kansas Avenue and via zoom to consider the following request:

Telephonic conferencing capabilities will be utilized to allow member of the public to participate remotely via Toll Free Dial In Number: +1 346 248 7799; Meeting ID: 832 0582 2197

Members of the public who wish to participate in Public Hearing on an agenda item must send their name, address and phone number via email to karevalo@weslacotx.gov by 12:00 pm on February 3, 2021. A staff member will contact you with instructions via phone call to address your public comment.

REZONE REQUEST:

Ezequiel Reyna Jr. is requesting to rezone 3701 S. Westgate. Also being West Tract S330' & E440'-S495'-N990'FT 795 15 AC GR 14.77 AC NET, Hidalgo County, and Texas from R-2 Duplex and apartment district.to M-1 Mobile home subdivision district.

The public is hereby invited to attend and express their support or opposition to the request. You may also file a written notice supporting or protesting this action. For more information please call the Planning Department at (956) 447-3403.


Si desea información en español, por favor llame al departamento de Planeación de la ciudad de Weslaco, (956) 447-3403.

Sincerely,

Rebekah de la Fuente, CFM
Planning Director

CITY OF WESLACO

Engineering Department



Ezequiel Reyan Jr.

**3701 South Westgate Dr.
WEST TRACT S330' & E440'-S495'-N990'
FT 795 15 AC GR 14.77 AC NET
Block 66, F.T. 795**

Purpose for the Rezoning request

Existing zoning: R-2
Existing land use: Multifamily
Proposed zoning: M-1
Proposed land use: Mobile Home Subdivision



City of Weslaco Code Enforcement Dept.

JAN 21, 2021

PIATER ERIC W 1310 TIERRA ENCANTADA WESLACO TX 78596-5869	T5438-01-003-0023-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 23 BLK 3 1310 TIERRA ENCANTADA	L: 30856 B: 203796
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0024-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 24 BLK 3 1314 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0025-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 25 BLK 3 1318 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0026-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 26 BLK 3 1402 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0027-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 27 BLK 3 1406 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0028-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 28 BLK 3 1410 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0029-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 29 BLK 3 1414 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0030-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 30 BLK 3 1502 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0031-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 31 BLK 3 1506 TIERRA ENCANTADA	L: 16748 B: 0
REYNA, EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	T5438-01-003-0032-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 32 BLK 3 1510 TIERRA ENCANTADA	L: 16748 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0033-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 33 BLK 3 1514 TIERRA ENCANTADA	L: 16748 B: 0
GONZALEZ SANTIAGO JR & LOIS 1307 S CLOSNER EDINBURG TX 78539-5665	T5438-01-003-0034-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 34 BLK 3 1518 TIERRA ENCANTADA	L: 16748 B: 0

City of Weslaco Code Enforcement Dept.

JAN 21, 2021

DK III CONSTRUCTION INC 704 W EXPRESSWAY 83 STE 100 WESLACO TX 78599	T5438-01-003-0035-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 35 BLK 3 1522 TIERRA ENCANTADA	L: 16748 B: 163085
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0036-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 36 BLK 3 1602 TIERRA ENCANTADA	L: 19411 B: 0
HANDY MODESTO & PRISCILLA K 3802 TIERRA DE ORO WESLACO TX 78596-8551	T5438-01-003-0037-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 37 BLK 3 3802 TIERRA DE ORO	L: 37206 B: 231924
REYNA EZEQUIEL JR 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0038-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 38 BLK 3 3806 TIERRA DE ORO	L: 17665 B: 0
SOLIS PEDRO OSCAR JR & MARTHA A 3810 TIERRA DE ORO WESLACO TX 78596-8551	T5438-01-003-0039-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 39 BLK 3 3810 TIERRA DE ORO	L: 31552 B: 213376
CASTILLO, ISMAEL PO BOX 861 PROGRESO TX 78579-0861	T5438-01-003-0065-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 65 BLK 3 3836 CIELO BLANCO	L: 27718 B: 0
PERALES JULIO 808 E 27TH ST WESLACO TX 78596-8105	T5438-01-003-0071-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 71 BLK 3 3802 CIELO BLANCO	L: 28246 B: 0
MILAN WHERTER CRUZ & MARIA N 501 N BRIDGE ST PMB 402 HIDALGO TX 78557-2530	T5438-01-003-0072-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 72 BLK 3 3805 TIERRA DE ORO	L: 25978 B: 0
PHARR LEASING GROUP LLC 1543 DUSTY CANYON HENDERSON NV 89052-3161	T5438-01-005-0001-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 1 BLK 5 3802 LAGOS VERDES	L: 59366 B: 0
DAY LAWRENCE 1543 DUSTY CANYON ST HENDERSON NV 89052-3161	T5438-01-005-0009-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 9 BLK 5 3834 LAGOS VERDES	L: 70079 B: 0
NEW YORK LIFE INSURANCE & 1661 WORTHINGTON RD SUITE 100 WEST PALM BEACH FL 33409-6493	T5438-01-005-0010-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 10 BLK 5 1210 HACIENDA DEL SOL	L: 71230 B: 502518
MCCANN DAVID R & HANNAH B 3809 TIERRA ESCONDIDA WESLACO TX 78596-3789	T5438-02-003-0022-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 2 LOT 22 BLK 3 3809 TIERRA ESCONDIDO	L: 25471 B: 190219

City of Weslaco Code Enforcement Dept.

JAN 21, 2021

WESLACO ISD PO BOX 2916 MCALLEN TX 78502-2916	T5438-02-003-0055-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 2 LOT 55 BLK 3 3810 TIERRA ESCONDIDO	L: 23742 B: 0
NEGRETE MIGUEL A 1601 W BUSINESS 83 STE B WESLACO TX 78596-5503	T5438-02-003-0056-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 2 LOT 56 BLK 3 3830 B SHEA	L: 31923 B: 0
JONES JEFFERY A & DIANA 3800 B SHEA WESLACO TX 78596-9519	T5438-02-003-0064-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 2 LOT 64 BLK 3 3800 B SHEA	L: 32381 B: 198848
GARCIA JULIO & MARYSOL 3402 S WESTGATE DR WESLACO TX 78596-4480	W3800-00-790-0000-03 WEST TRACT E266'-N818.03' FT 790 5.01AC GR 4.52AC NET 3402 S WESTGATE DR	L: 60907 B: 99754
COTTONFIELDS, LTD 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-790-0000-05 WEST TRACT E1065'-S501.97' FT 79 0 12.27 AC GR 11.92 AC NET 3700 S WESTGATE DR	L: 0 B: 0
REYNA, EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-791-0000-00 WEST TRACT 15.67AC BNG 2 IRR TRS FT 791 GOLF COURSE	L: 124106 B: 569416
REYNA, EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-794-0000-00 WEST TRACT 11.89AC-FT 794 GOLF C OURSE 0 TIERRA SANTA BLVD	L: 56501 B: 33000
MENA OSCAR JR & MELISSA 3611 S WESTGATE DR WESLACO, TX 78596	W3800-00-795-0000-08 WEST TRACT W440'-S99'-N891' FT 7 95 1AC GR 0.93AC NET 3611 S WESTGATE DR	L: 27555 B: 0
LOPEZ MELECIO 1005 MARITZA ST WESLACO TX 78596-2078	W3800-00-795-0000-24 WEST TRACT W440'-S99'-N792' FT 7 95 1AC GR 0.93AC NET 3609 S WESTGATE DR	L: 27555 B: 0
GARZA AMERICO & ARISTEO 3621 S WESTGATE DR WESLACO TX 78596-9479	W3800-00-795-0000-56 WEST TRACT W440'-S99'-N990' FT 7 95 1AC GR 0.93AC NET 3621 S WESTGATE	L: 27555 B: 8388
VASQUEZ ARTURO & FRANCES RR 2 BOX 523A WESLACO TX 78596	W3800-00-795-0000-72 WEST TRACT W220'-E660'-N990' FT 795 5.0AC GR 4.85AC NET 0 MILE 5 NORTH	L: 0 B: 108
SANCHEZ OLGA RR 7 BOX 152F WESLACO TX 78596	W3800-00-795-0000-75 WEST TRACT E220'-W660'-S210.50'- N594' FT 795 1.06AC 0 MILE 5 NORTH	L: 10070 B: 19793

City of Weslaco Code Enforcement Dept.

JAN 21, 2021

COTTONFIELDS, LTD 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-795-0000-80 WEST TRACT S330' & E440'-S495'-N 990' FT 795 15 AC GR 14.77 AC NE 0 S WESTGATE DR	L: 23750 B: 72106
MW PETROLEUM CORP 2000 POST OAK BLVD STE 100 HOUSTON TX 77056-4497	W3800-00-795-0000-96 WEST TRACT E440'-N495' FT 795 5. 0AC GR 4.70AC NET 1301 W MI 5 N RD	L: 104420 B: 3300
RODRIGUEZ ADRIAN & LIDIA 1421 W MILE 5 N WESLACO TX 78596-4697	W3800-00-795-0000-97 WEST TRACT E200'-W660'-S96'-N990 ' FT 795 0.44AC NET 1421 W 34TH ST	L: 20145 B: 12711
REYNA, EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-796-0000-00 WEST TRACT 22.87AC GOLF COURSE F T 796 22.87AC GR 22.78AC NET 0 MILE 5 NORTH RD	L: 151487 B: 33000
REYNA, EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-797-0000-05 WEST TRACT 18.20AC-FT 797 GOLF C OURSE 0 BORDER AVE	L: 78624 B: 35000



Planning & Zoning Commission Standardized Agenda Request Form

Date of Meeting: February 3, 2021	Agenda Item No. (to be assigned by PCE): IV. B.
From: Rebekah de la Fuente, Planning Director, on behalf of Ezequiel Reyna Jr.	
Subject/Agenda Item: Discussion and consideration to approve rezone 3702 S. Westgate. Also being West Tract E1065'-S501.97' Farm Tract 790 being 12.27 AC GR 11.92 AC NET Hidalgo County, and Texas from R-2 Duplex and apartment district.to M-1 Mobile home subdivision district.	
Discussion/Overview: The applicant is requesting to rezone property from R-2 Duplex and apartment district.to M-1 Mobile home subdivision district. Notice of the application and the Public Hearing for the Planning and Zoning Commission appeared in The Monitor on January 18, 2021. Forty (40) property owners within 200 feet of the applicant's property were notified by letter on January 22, 2021.	
Staff recommendation for Commission's Action: Staff recommends denial based on surrounding land use and 2040 land use map.	
Additional Action Prompted: [X] Mayor's Signature [X] Public Hearing [] Budget Amendment [] Resolution [x] Ordinance – First Reading [x] Ordinance – Final Reading	
Advisory Review, (if any): (name of board/committee, date of action, recommendation): N/A	
If item previously considered, provide date and action by Commission: N/A	
Attachments,(if any): Application for rezone with attachments.	
Responsibilities upon Commission's Action: Planning staff will advise applicant.	



APPLICATION FOR REZONING

The Planning & Zoning Commission meets every 1st Wednesday of each month at 5:30 pm.

The City Commission meets every 1st and 3rd Tuesday of each month at 5:30 pm

FILE NO. _____

PROPOSED PROJECT

Legal Description of Property to be rezoned:

Lot West Tract E 1065-S 501.97 FT 9012.27 AC GR Block 1162 AC Net

Subdivision Name _____

Street Address Westgate Dr. 3702 S Westgate.

Existing Zoning R-2 multi Existing Land Use _____

Proposed Zoning M-1 Proposed Land Use _____

_____ \$305.00 non-refundable filing fee.

_____ Detailed dimensioned site plan/map must be submitted with this request.

_____ Survey and metes and bounds if the legal description is a portion of a lot.

_____ City and school tax receipts attached.

_____ I have received a copy of "The Intent of Zoning Application Instructions".

APPLICANT

Name Ezequiel Reyna Jr. Phone (956) 968-2829

Address 702 W. Expressway 83 Fax: (956) 964-9634

City Weslaco State TX Zip Code 78599 E-Mail: Sonia.reynapro@gmail.com

OWNER

Name Ezequiel Reyna Jr. Phone (956) 968-2829

Address 702 W. Expressway 83 Fax: (956) 964-9634

City Weslaco State TX Zip Code 78599 E-Mail: Sonia.reynapro@gmail.com

I certify that I am the actual owner of the property described above and this application is being submitted with my consent (include corporate name if applicable); or I am authorized by the actual owner to submit this application and have attached written evidence of such authorization.

Signature _____ Date 1/8/21

Signature _____ Date _____
Applicant

Signature _____ Date _____
Authorized Agent

City of Weslaco

"The City on the Grow"



David Suarez, Mayor
Leo Muñoz, Mayor Pro-Tem, District 1
Greg Kerr, Commissioner, District 2
Jose "J.P." Rodriguez, Commissioner, District 3
Adrian Farias, Commissioner, District 4
Letty Lopez, Commissioner, District 5
Josh Pedraza, Commissioner, District 6

Mike R. Perez, City Manager

PLANNING DEPARTMENT

January 22, 2021

Legal Notice

Dear Occupant:

The Weslaco Planning and Zoning Commission will hold a public hearing on Wednesday, February 3, 2021, and the City Commission will hold a public hearing on February 16, 2021 at 5:30 p.m. at the City Hall Legislative Chambers located at 255 South Kansas Avenue and via zoom to consider the following request:

Telephonic conferencing capabilities will be utilized to allow member of the public to participate remotely via Toll Free Dial In Number: +1 346 248 7799; Meeting ID: 832 0582 2197

Members of the public who wish to participate in Public Hearing on an agenda item must send their name, address and phone number via email to karevalo@weslacotx.gov by 12:00 pm on February 3, 2021. A staff member will contact you with instructions via phone call to address your public comment.

REZONE REQUEST:

Ezequiel Reyna Jr. is requesting to rezone 3702 S. Westgate. Also being West Tract E1065'-S501.97' Farm Tract 790 being 12.27 AC GR 11.92 AC NET Hidalgo County, and Texas from R-2 Duplex and apartment district. to M-1 Mobile home subdivision district.

The public is hereby invited to attend and express their support or opposition to the request. You may also file a written notice supporting or protesting this action. For more information please call the Planning Department at (956) 447-3403.


Si desea información en español, por favor llame al departamento de Planeación de la ciudad de Weslaco, (956) 447-3403.

Sincerely,

Rebekah de la Fuente, CFM
Planning Director

CITY OF WESLACO

Engineering Department



Ezequiel Reyán Jr.

**3702 South Westgate Drive
WEST TRACT E1065'-S501.97' FT 790
12.27 AC GR 11.92 AC NET
LOT 1, BLOCK 175, F.T. 790**

Purpose for the Rezoning request

Existing zoning: R-2
Existing land use: Multifamily
Proposed zoning: M-1
Proposed land use: Mobile Home Subdivision



City of Weslaco Code Enforcement Dept.

JAN 21, 2021

LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0016-00 LAS VILLAS AT TIERRA SANTA LOT 1 6 BLK 2 0 LA PAZ	L: 10759 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0017-00 LAS VILLAS AT TIERRA SANTA LOT 1 7 BLK 2 0 LAS CRUCES	L: 11297 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0018-00 LAS VILLAS AT TIERRA SANTA LOT 1 8 BLK 2 0 LAS CRUCES	L: 10018 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0019-00 LAS VILLAS AT TIERRA SANTA LOT 1 9 BLK 2 0 LAS CRUCES	L: 10018 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0020-00 LAS VILLAS AT TIERRA SANTA LOT 2 0 BLK 2 0 LAS CRUCES	L: 10018 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0021-00 LAS VILLAS AT TIERRA SANTA LOT 2 1 BLK 2 0 LAS CRUCES	L: 10018 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0022-00 LAS VILLAS AT TIERRA SANTA LOT 2 2 BLK 2 0 LAS CRUCES	L: 10018 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0023-00 LAS VILLAS AT TIERRA SANTA LOT 2 3 BLK 2 0 LAS CRUCES	L: 10018 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0024-00 LAS VILLAS AT TIERRA SANTA LOT 2 4 BLK 2 0 LAS CRUCES	L: 10018 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0025-00 LAS VILLAS AT TIERRA SANTA LOT 2 5 BLK 2 0 LAS CRUCES	L: 10209 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0026-00 LAS VILLAS AT TIERRA SANTA LOT 2 6 BLK 2 0 LAS CRUCES	L: 9683 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0027-00 LAS VILLAS AT TIERRA SANTA LOT 2 7 BLK 2 0 LAS CRUCES	L: 12080 B: 0

City of Weslaco Code Enforcement Dept.

JAN 21, 2021

LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0028-00 LAS VILLAS AT TIERRA SANTA LOT 2 8 BLK 2 0 LA LUZ	L: 12497 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0029-00 LAS VILLAS AT TIERRA SANTA LOT 2 9 BLK 2 0 LA LUZ	L: 7716 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0030-00 LAS VILLAS AT TIERRA SANTA LOT 3 0 BLK 2 0 LA LUZ	L: 9703 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0050-00 LAS VILLAS AT TIERRA SANTA LOT 5 0 BLK 2 0 LA LUZ	L: 12180 B: 0
LAS VILLAS AT TIERRA SANTA 5221 N MCCOLL RD MCALLEN TX 78504-2202	L3394-00-002-0051-00 LAS VILLAS AT TIERRA SANTA LOT 5 1 BLK 2 0 LA PAZ	L: 12180 B: 0
HANDY MODESTO & PRISCILLA K 3802 TIERRA DE ORO WESLACO TX 78596-8551	T5438-01-003-0037-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 37 BLK 3 3802 TIERRA DE ORO	L: 37206 B: 231924
REYNA EZEQUIEL JR 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599-4379	T5438-01-003-0038-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 38 BLK 3 3806 TIERRA DE ORO	L: 17665 B: 0
RAMIREZ ANA LIZA 20003 MASON CREEK DR KATY TX 77449-2203	T5438-01-02A-0018-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 18 BLK 2A 3806 SANTO CIELO	L: 11078 B: 127955
ORTEGON JAY R 2018 LAS CRUCES AVE WESLACO TX 78596-8513	T5438-01-02A-0019-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 19 BLK 2A 2018 LAS CRUCES AVE	L: 16626 B: 118328
GONZALEZ MARISELA 2014 LAS CRUCES ST WESLACO TX 78596	T5438-01-02A-0020-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 20 BLK 2A 2014 LAS CRUCES AVE	L: 18627 B: 101001
GONZALEZ MARIA N 306 LAKEWAY DR WESLACO TX 78596-1865	T5438-01-02A-0021-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 21 & 22 BLK 2A 2010 LAS CRUCES AVE	L: 14616 B: 0
REYNA EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78599	T5438-01-02A-0022-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 22 BLK 2A 2006 LAS CRUCES AVE	L: 7308 B: 0

City of Weslaco Code Enforcement Dept.

JAN 21, 2021

BREMONT ALICIA LIZETH J 1901 CLUB DE AMISTAD WESLACO TX 78596-8576	T5438-01-02A-0023-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 23 BLK 2A 2002 LAS CRUCES AVE	L: 10513 B: 0
ARAUJO JUAN M GANTE 1601 TRAILER LN LOT 121 IRONDALE AL 35210	T5438-01-02A-0024-00 TIERRA SANTA GOLF CLB & COMMUNIT Y PH 1 LOT 24 BLK 2A 3805 SANTO CIELO	L: 12725 B: 0
MORENO HECTOR MANUEL SOBRON 313 E COMA AVE STE 579 HIDALGO TX 78557-2506	W3800-00-790-0000-00 WEST TRACT W 255' FT 790 7.73 GR 7.61AC NET 2029 W MI 5 N RD	L: 72295 B: 0
CABRERA FRANCISCO 1725 MILE 5 NORTH WESLACO TX 78596	W3800-00-790-0000-01 WEST TRACT W266'-E532'-N818.03'- FT 790 5.00AC GR 4.88AC NET 0 MILE 5 NORTH	L: 65758 B: 49340
LA CASA DE ORACION 1917 W MILE 5 N WESLACO TX 78596-5057	W3800-00-790-0000-02 WEST TRACT W267'-E1065'-N818.03' FT 790 5.01AC GR 4.89AC NET 1919 W MI 5 N RD	L: 108641 B: 0
GARCIA JULIO & MARYSOL 3402 S WESTGATE DR WESLACO TX 78596-4480	W3800-00-790-0000-03 WEST TRACT E266'-N818.03' FT 790 5.01AC GR 4.52AC NET 3402 S WESTGATE DR	L: 60907 B: 99754
COTTONFIELDS, LTD 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-790-0000-05 WEST TRACT E1065'-S501.97' FT 79 0 12.27 AC GR 11.92 AC NET 3700 S WESTGATE DR	L: 0 B: 0
ABELDANO PABLO & ALICE 1801 W MILE 5 N WESLACO TX 78596-9518	W3800-00-790-0000-09 WEST TRACT W266'-E798'-S204.5'-N 818.03' & W60'-E592'-N613.5' FT 1801 W MILE 5 RD	L: 44381 B: 32989
CARRIZALES RAYMUNDO 1805 W MILE 5 N WESLACO TX 78596-9518	W3800-00-790-0000-10 WEST TRACT W206'-E798'-S204.5'-N 613.5' & W60'-E652'-N613.5' FT 7 1805 W MILE 5 RD	L: 40379 B: 81332
REYNA, EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-791-0000-00 WEST TRACT 15.67AC BNG 2 IRR TRS FT 791 GOLF COURSE	L: 124106 B: 569416
REYNA, EZEQUIEL JR & LIVIA 702 W EXPRESSWAY 83 STE 100 WESLACO TX 78596-4379	W3800-00-794-0000-00 WEST TRACT 11.89AC-FT 794 GOLF C OURSE 0 TIERRA SANTA BLVD	L: 56501 B: 33000
MENA OSCAR JR & MELISSA 3611 S WESTGATE DR WESLACO, TX 78596	W3800-00-795-0000-08 WEST TRACT W440'-S99'-N891' FT 7 95 1AC GR 0.93AC NET 3611 S WESTGATE DR	L: 27555 B: 0

City of Weslaco Code Enforcement Dept.


JAN 21, 2021

GARCIA ISMAEL & NELDA G	W3800-00-795-0000-16	L: 27555
3605 S WESTGATE DR	WEST TRACT W440'-S99'-N693' FT 7	B: 83144
WESLACO TX 78596-9479	95 1AC GR 0.93AC NET	
	0 S WESTGATE DR	
LOPEZ MELECIO	W3800-00-795-0000-24	L: 27555
1005 MARITZA ST	WEST TRACT W440'-S99'-N792' FT 7	B: 0
WESLACO TX 78596-2078	95 1AC GR 0.93AC NET	
	3609 S WESTGATE DR	
GARZA AMERICO & ARISTEO	W3800-00-795-0000-56	L: 27555
3621 S WESTGATE DR	WEST TRACT W440'-S99'-N990' FT 7	B: 8388
WESLACO TX 78596-9479	95 1AC GR 0.93AC NET	
	3621 S WESTGATE	
COTTONFIELDS, LTD	W3800-00-795-0000-80	L: 23750
702 W EXPRESSWAY 83 STE 100	WEST TRACT S330' & E440'-S495'-N	B: 72106
WESLACO TX 78596-4379	990' FT 795 15 AC GR 14.77 AC NE	
	0 S WESTGATE DR	



Planning & Zoning Commission Standardized Agenda Request Form

Date of Meeting: February 3, 2021	Agenda Item No. (to be assigned by PCE): IV. C.
From: Rebekah de la Fuente, Planning Director, on behalf of Rush Transportation L.L.C	
Subject/Agenda Item: Discussion and consideration to approve rezone 703 & 705 W. 6th St. Also being lot 24 & 25, Block 4, Glendale Addition, Hidalgo County, and Texas from R-1 One-family dwelling to R-2 Duplex and apartment district.	
Discussion/Overview: The applicant is requesting to rezone property from R-1 One-family dwelling to R-2 Duplex and apartment district. Notice of the application and the Public Hearing for the Planning and Zoning Commission appeared in The Monitor on January 18, 2021. Thirty (30) property owners within 200 feet of the applicant's property were notified by letter on January 22, 2021.	
Staff recommendation for Commission's Action: Staff recommends approval based on surrounding land use.	
Additional Action Prompted: [X] Mayor's Signature [X] Public Hearing [] Budget Amendment [] Resolution [x] Ordinance – First Reading [x] Ordinance – Final Reading	
Advisory Review, (if any): (name of board/committee, date of action, recommendation): N/A	
If item previously considered, provide date and action by Commission: N/A	
Attachments,(if any): Application for rezone with attachments.	
Responsibilities upon Commission's Action: Planning staff will advise applicant.	



APPLICATION FOR REZONING

The Planning & Zoning Commission meets every 1st Wednesday of each month at 5:30 pm.

The City Commission meets every 1st and 3rd Tuesday of each month at 5:30 pm

FILE NO. _____

PROPOSED PROJECT

Legal Description of Property to be rezoned:

Lot 24 & 25 Block 4

Subdivision Name Glendale Addition

Street Address 703 & 705 W 6th St.

Existing Zoning R 1 Single Family Existing Land Use R 1

Proposed Zoning R 2 Multi Family Proposed Land Use R 2

- ☒ \$305.00 non-refundable filing fee.
- ☒ Detailed dimensioned site plan/map must be submitted with this request.
- ☒ Survey and metes and bounds if the legal description is a portion of a lot.
- ☒ City and school tax receipts attached.
- ☒ I have received a copy of "The Intent of Zoning Application Instructions".

APPLICANT

Name Rush Transportation L.L.C.
Ricardo Robles Phone Please Email

Address 1008 E. Pecan Blvd. Fax: N.A.

City McAllen State Tx Zip Code 78501 E-Mail: roblesrick44@yahoo.com

OWNER

Name Rush Transportation L.L.C. Phone Please Email

Address 1008 E. Pecan Blvd. Fax: N.A.

City McAllen State Tx Zip Code 78501 E-Mail: roblesrick44@yahoo.com

I certify that I am the actual owner of the property described above and this application is being submitted with my consent (include corporate name if applicable); or I am authorized by the actual owner to submit this application and have attached written evidence of such authorization.

Signature Ricardo Robles Date 1/10/21
Owner


Signature _____ Date _____
Applicant

Signature _____ Date _____
Authorized Agent

- LEGEND**
- Found 1/2" iron rod
 - ✱ Found 1/2" iron rod with a plastic cap stamped "PENA"
 - ✱ Chainlink fence
 - ✱ Hogwire fence
 - Found 1/2" iron pipe

20486

BASIS OF BEARINGS:
1/2" I.R. FND. AT
S.E. COR. LOT 26 &
1/2" I.P. FND. AT
S.W. COR. LOT 24



**SURVEY PLAT OF
LOTS 24 AND 25, BLOCK 4
GLENDALE ADDITION
AN ADDITION TO THE CITY OF WESLACO
HIDALGO COUNTY, TEXAS**
PER MAP RECORDED IN VOLUME 5, PAGE 3, H.C.M.R.

I, REYNALDO ROBLES, REGISTERED PROFESSIONAL LAND SURVEYOR OF THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THE ABOVE PLAT REPRESENTS A SURVEY AS MADE ON THE GROUND UNDER MY SUPERVISION, THAT IT REPRESENTS THE FACTS FOUND ON THE GROUND AT THE TIME OF SURVEY AND THAT THERE ARE NO VISIBLE DISCREPANCIES, CONFLICTS, OR SHORTAGES IN AREA OR BOUNDARY LINES, OR ANY ENCROACHMENTS OR OVERLAPPING OF IMPROVEMENTS OR VISIBLE EASEMENTS EXCEPT AS SHOWN AND BY GRAPHIC PLOTTING ONLY THIS PROPERTY LIES IN FLOOD ZONE "B" (AREAS BETWEEN LIMITS OF THE 100-YEAR FLOOD AND 500-YEAR FLOOD; OR CERTAIN AREAS SUBJECT TO 100-YEAR FLOODING WITH AVERAGE DEPTHS LESS THAN ONE FOOT OR WHERE THE CONTRIBUTING DRAINAGE AREA IS LESS THAN ONE SQUARE MILE; OR AREAS PROTECTED BY LEVEES FROM THE BASEFLOOD OF FIRM COMMUNITY PANEL No. 480349 0005 B. DATED MARCH 4, 1992.

PROPERTY ADDRESS: 703 AND 705 6TH ST.
WESLACO, TX 78596

PREPARED FOR: RICK ROBLES

RA ROBLES AND ASSOCIATES, PLLC

PROFESSIONAL LAND SURVEYORS

P.O. BOX 476
107 W. HUISACHE ST.
WESLACO, TEXAS 78596

PHONE (956) 968-2422
FAX (956) 969-2011
FIRM No. 10096700

SURVEYED: 08-05-2020

DRAWN BY: PG/08-06-2020

SCALE: 1"=40'

JOB No. 20486

TITLE COMMITMENT No.

REVISED:

SURVEY IS VALID ONLY IF PRINT HAS ORIGINAL EMBOSSED SEAL OF SURVEYOR OF RECORD.

© COPYRIGHT 2020

REYNALDO ROBLES, R.P.L.S. #4032

THIS SURVEY WAS PREPARED WITHOUT THE BENEFIT OF A TITLE REPORT. EASEMENTS OF RECORD MAY AFFECT SUBJECT PROPERTY.

City of Weslaco

"The City on the Grow"



David Suarez, Mayor
Leo Muñoz, Mayor Pro-Tem, District 1
Greg Kerr, Commissioner, District 2
Jose "J.P." Rodriguez, Commissioner, District 3
Adrian Farias, Commissioner, District 4
Letty Lopez, Commissioner, District 5
Josh Pedraza, Commissioner, District 6

Mike R. Perez, City Manager

PLANNING DEPARTMENT

January 22, 2021

Legal Notice

Dear Occupant:

The Weslaco Planning and Zoning Commission will hold a public hearing on Wednesday, February 3, 2021, and the City Commission will hold a public hearing on February 16, 2021 at 5:30 p.m. at the City Hall Legislative Chambers located at 255 South Kansas Avenue and via zoom to consider the following request:

Telephonic conferencing capabilities will be utilized to allow member of the public to participate remotely via Toll Free Dial In Number: +1 346 248 7799; Meeting ID: 832 0582 2197

Members of the public who wish to participate in Public Hearing on an agenda item must send their name, address and phone number via email to karevalo@weslacotx.gov by 12:00 pm on February 3, 2021. A staff member will contact you with instructions via phone call to address your public comment.

REZONE REQUEST:

Rush Transportation L.L.C. is requesting to rezone 703 & 705 W. 6th St. Also being lot 24 & 25, Block 4, Glendale Addition, Hidalgo County, and Texas from R-1 One-family dwelling to R-2 Duplex and apartment district.

The public is hereby invited to attend and express their support or opposition to the request. You may also file a written notice supporting or protesting this action. For more information please call the Planning Department at (956) 447-3403.


Si desea información en español, por favor llame al departamento de Planeación de la ciudad de Weslaco, (956) 447-3403.

Sincerely,

Rebekah de la Fuente, CFM
Planning Director

CITY OF WESLACO

Engineering Department



Rush Transportation L.L.C.

703 and 705 West 6th Street

**GLENDAL ADDITION LOTS 24 & 25 BLK 4
LOT 18, BLOCK 163, F.T. 1508**

Purpose for the Rezoning request

Existing zoning: R-1
Existing land use: Single Family
Proposed zoning: R-2
Proposed land use: Multifamily



City of Weslaco Code Enforcement Dept.

JAN 21, 2021

SUMMY, KENNETH R & LAURA A 501 W 15TH ST WESLACO TX 78596-7433	G4100-00-003-0010-00 GLENDALE LOT 10 BLK 3 608 6TH ST	L: 18600 B: 19568
SALINAS, FORTINA V 515 TULA AVE WESLACO TX 78596-5833	G4100-00-003-0011-00 GLENDALE LOT 11 BLK 3 515 TULA AVE	L: 18600 B: 12938
GRIMALDO SOSTENES & DORA V 513 TULA AVE WESLACO TX 78596-5833	G4100-00-003-0012-00 GLENDALE LOT 12 BLK 3 513 TULA AVE	L: 18600 B: 9076
JIMENEZ, ALEX 511 TULA AVE WESLACO TX 78596-5833	G4100-00-003-0013-00 GLENDALE LOT 13 BLK 3 511 TULA AVE	L: 18600 B: 20900
ORTIZ, RENE, JR 509 TULA AVE WESLACO TX 78596-5833	G4100-00-003-0014-00 GLENDALE LTS 14-15 BLK 3 509 TULA AVE	L: 35400 B: 76971
LOPEZ RUBY 2236 W MILE 13 1/2 N WESLACO TX 78599-9290	G4100-00-003-0016-00 GLENDALE LOT 16 BLK 3 505 TULA AVE	L: 18600 B: 34079
CRUZ ELENA 608 N HUTTO RD DONNA TX 78537-9020	G4100-00-004-0001-00 GLENDALE LTS 1-2 BLK 4 701 STONE ST	L: 38350 B: 19066
RIOS, ENRIQUE & ELENA 707 STONE ST WESLACO TX 78596-5831	G4100-00-004-0003-05 GLENDALE LOT 3 BLK 4	L: 20800 B: 10766
RIOS, ENRIQUE & ELENA 707 STONE ST WESLACO TX 78596-5831	G4100-00-004-0004-00 GLENDALE LOT 4 BLK 4 & LOT 3 707 STONE ST	L: 38350 B: 40729
HINOJOSA EDEN & BERTA A 709 STONE ST WESLACO TX 78596-5831	G4100-00-004-0005-00 GLENDALE LT 5 BLK 4 709 STONE ST	L: 17329 B: 15417
RAMOS SYLVIA & CAMILO JR 711 STONE ST WESLACO TX 78596-5831	G4100-00-004-0006-00 GLENDALE LT 6 BLK 4 711 STONE ST	L: 20150 B: 15381
VELA ADAN 713 STONE ST WESLACO TX 78596-5831	G4100-00-004-0007-00 GLENDALE LOT 7 BLK 4 713 STONE ST	L: 20150 B: 30925

City of Weslaco Code Enforcement Dept.

JAN 21, 2021

YBARRA MANAEN & ARTURO DE 715 STONE ST WESLACO TX 78596-5831	G4100-00-004-0008-00 GLENDALE LTS 8 & E 1/2 LOT 9 BLK 4 715 STONE ST	L: 30225 B: 35741
MARTINEZ, ARMANDO L & ANNA PO BOX 1769 WESLACO TX 78599-1769	G4100-00-004-0019-00 GLENDALE LTS E 12 1/2-19 ALL 20 BLK 4 805 W 6TH	L: 26000 B: 17428
TREVINO RUPERTO LOPEZ PO BOX 669 LA BLANCA TX 78558-0669	G4100-00-004-0021-00 GLENDALE LT 21 BLK 4 803 W 6TH ST	L: 20150 B: 17725
GALLEGOS DAGOBERTO & HILDA E 801 W 6TH ST WESLACO TX 78596-5807	G4100-00-004-0022-00 GLENDALE LOT 22 BLK 4 801 W 6TH ST	L: 20150 B: 13487
RODRIGUEZ, BEATRICE 707 W 6TH WESLACO TX 78596-5805	G4100-00-004-0023-00 GLENDALE LT 23 BLK 4 707 W 6TH ST	L: 20150 B: 21034
RUSH TRANSPORTATION LLC 315 N SHARY RD STE 1040 MISSION TX 78572-8223	G4100-00-004-0024-00 GLENDALE LTS 24,25 BLK 4 705 W 6TH ST	L: 38350 B: 12439
ROBLES REYNALDO & ALMA D PO BOX 476 WESLACO TX 78599-0476	G4100-00-004-0026-00 GLENDALE LOT 26 BLK 4 700 W 6TH ST	L: 20150 B: 9822
MARTINEZ, ALFREDO & GRACIE 708 STONE ST WESLACO TX 78596-5832	G4100-00-005-0024-00 GLENDALE LOT 24 BLK 5	L: 21313 B: 77142
RODRIGUEZ MARIA ELIZABETH 706 STONE ST WESLACO TX 78596-5832	G4100-00-005-0025-00 GLENDALE LT 25 BLK 5 706 STONE ST	L: 21313 B: 28999
CITY OF WESLACO 255 S KANSAS AVE WESLACO TX 78596-6158	G4100-00-005-0026-00 GLENDALE LOTS 26 & 27 BLK 5 0 STONE ST	L: 46750 B: 0
PUGA DALIA SOLIS 504 TULA AVE WESLACO TX 78596-5834	G4100-00-005-0028-00 GLENDALE LT 28 BLK 5 504 TULA AVE	L: 21313 B: 14282
JOHNSON CHARLES C & LINA F 600 S GEORGIA AVE WESLACO TX 78596-6842	P6600-00-001-0001-00 PIKE HOOK BLK 1 LT 1 600 S GEORGIA ST	L: 37136 B: 55084

City of Weslaco Code Enforcement Dept.

JAN 21, 2021

MONTES LEONARDO III & DELILA 2013 DE LEON AVE DONNA TX 78537-3746	P6600-00-001-0002-00 PIKE HOOK BLK 1 LT 2 604 S GEORGIA ST	L: 25392 B: 59890
BARRERA LISA V 601 S OHIO AVE WESLACO TX 78596-6837	P6600-00-001-0010-00 PIKE HOOK BLK 1 LT 10 601 S OHIO	L: 38610 B: 88818
TROPICAL TX CNTR FOR MENTAL 1425 S 9TH AVE EDINBURG TX 78539	Y2000-00-001-0001-00 YODER LOTS 1-3 & LOT 7 BLK 1 601 W 6TH ST	L: 95234 B: 113467
FUENTES, JOSE A & NORMA L 607 W 6TH ST WESLACO TX 78596-5803	Y2000-00-001-0004-00 YODER LOT 4 BLK 1 607 W 6TH ST	L: 20708 B: 29247
PAYNE E M 2401 E EXPRESSWAY 83 WESLACO TX 78599-5512	Y2000-00-001-0005-00 YODER LOT 5 & 6 BLK 1 609 W 6TH ST	L: 46176 B: 111824
GIVILANCZ, MIKE JR & GLORI 609 W 6TH ST WESLACO TX 78596-5803	Y2000-00-001-0006-00 YODER W 10'-LOT 5, ALL LOT 6 BLK 1 0 6TH ST	L: 26390 B: 0



Planning & Zoning Commission Standardized Agenda Request Form

Date of Meeting: February 3, 2021	Agenda Item No. (to be assigned by PCE): IV. D.
From: Rebekah de la Fuente, Planning Director, on behalf of Ricardo Guerra.	
Subject/Agenda Item: Discussion and consideration to approve Conditional Use Permit to obtain an Off-Premise Wine and Beer Retailer's Permit at 2720 N Westgate, also being Lot 1 & 2, Block 5, Sun Country Estates Subdivision, Hidalgo County, and Texas. Possible Action.	
Discussion/Overview: The applicant is requesting to obtain a Conditional Use Permit to obtain an Off-Premise Wine and Beer Retailer's Permit at 2720 N Westgate, also being Lot 1 & 2, Block 5, Sun Country Estates Subdivision, Hidalgo County, and Texas. Notice of the application and the public hearing for the Planning and Zoning Commission and the City Commission appeared in The Monitor on January 18, 2021. Twenty-two (22) property owners within 200 feet of the applicant's property were notified by letter on January 22, 2021.	
Staff recommendation for Commission's Action: Staff recommends approval.	
Additional Action Prompted: ☒ Mayor's Signature ☒ Public Hearing ☐ Budget Amendment ☐ Resolution ☒ Ordinance – First Reading ☒ Ordinance – Final Reading	
Advisory Review, (if any): (name of board/committee, date of action, recommendation): N/A	
If item previously considered, provide date and action by Commission: N/A	
Attachments,(if any): Application for Conditional Use Permit with attachments.	
Responsibilities upon Commission's Action: Planning staff will advise applicant.	



APPLICATION FOR CONDITIONAL USE PERMIT

The Planning & Zoning Commission meets every 1st Wednesday of each month at 5:30 pm.

The City Commission meets every 1st and 3rd Tuesday of each month at 5:30 pm

FILE NO. _____

RECEIVED

JAN 08 2021

Planning &
Code Enforcement Dept.

PROPOSED PROJECT

Legal Description of Property for which Conditional Use Permit is requested:

Lots 1 and 2 Block 5

Subdivision Name Sun Country Estates

Street Address 2720 N. Westgate Dr. Weslaco, TX 78599

Existing Zoning _____ Existing Land Use _____

Purpose for the Conditional Use Permit Request new Mead Market/convenience store

What, if anything, is planned to minimize the impact on the surrounding land uses: _____

_____ \$300.00 non-refundable filing fee.

_____ Detailed dimensioned site plan/map must be submitted with this request.

_____ Survey and metes and bounds if the legal description is a portion of a lot.

_____ City and school tax receipts attached.

_____ I have received a copy of "CUP Application Instructions"

APPLICANT

Name Ricardo R. Guerra Phone (956) 968-6773

Address 6700 N. Mile 3 1/2 W Fax: (956) 969-9674

City Weslaco State TX Zip Code 78599 E-Mail: n-quintanilla@yahoo.com

OWNER

Name Ricardo R. Guerra Phone (956) 968-6773

Address 6700 N. Mile 3 1/2 W Fax: (956) 969-9674

City Weslaco State TX Zip Code 78599 E-Mail: n-quintanilla@yahoo.com

To the best of your knowledge are there any deed restrictions, restrictive covenants, etc., which would prevent the utilization of the property in the manner indicated?

Yes _____ No ✓

I certify that I am the actual owner of the property described above and this application is being submitted with my consent or I am authorized by the actual owner to submit this application and have attached written evidence of such authorization.

Signature [Signature] Date 1-7-2021
Owner

Signature [Signature] Date 1-7-2021
Applicant

Signature _____ Date _____
Authorized Agent

STAFF USE ONLY

Accepted By _____ Payment Received By _____ Date Paid _____

Notice of Public Hearing Sent to Property Owners Within 200' of Proposed Site Date _____

P & Z Notice of Public Hearing Published in Newspaper Date _____

City Commission Notice of Public Hearing Published in Newspaper Date _____

Presented to P & Z Commission
Approved _____ Disapproved _____ Tabled _____ Date _____

Presented to City Commission
Approved _____ Disapproved _____ Tabled _____ Date _____

COPY

RECEIVED

JAN 08 2021



**TEXAS ALCOHOLIC
BEVERAGE COMMISSION**

Texans Helping Businesses & Protecting Communities

Planning &
Code Enforcement Dept.

**OFF-PREMISE
PREQUALIFICATION PACKET**

L-OFF (10/2020)

Submit this packet to the proper governmental entities to obtain certification for the type of license/permit for which you are applying as required by Sections 11.37, 11.39, 11.46(b), 61.37, 61.38, 61.42 and Rule §33.13
All statutory and rule references mentioned in this application refer to and can be found in the Texas Alcoholic Beverage Code or Rules located on our website. www.tabc.texas.gov/laws/code_and_rules.asp

LOCATION INFORMATION

1. Application for:			
☐ Original			
☐ Reinstatement	☐ Reinstatement and Change of Trade Name	License/Permit Number <u>BQ632106</u>	
☒ Change of Location	☐ Change of Location and Trade Name	License/Permit Number <u>BQ632106</u>	
2. Type of Off-Premise License/Permit			
☒ BQ Wine and Beer Retailer's Off-Premise Permit	☐ LP Local Distributor's Permit		
☐ BF Beer Retail Dealer's Off-Premise License	☐ E Local Cartage Permit		
☐ P Package Store Permit	☐ ET Local Cartage Transfer Permit		
☐ Q Wine Only Package Store Permit	☐ PS Package Store Tasting Permit		
3. Indicate Primary Business at this Location			
☒ Grocery/Market	☐ Convenience Store without Gas		
☐ Liquor Store	☐ Miscellaneous _____		
☐ Convenience Store with Gas			
4. Trade Name of Location (Name of store, business, etc.) WESTGATE MEAT MARKET			
5. Location Address 2720 N WESTGATE DR			
City WESLACO	County HIDALGO	State TX	Zip Code 78599
6. Mailing Address 6700 N MILE 3 1/2 W	City WESLACO	State TX	Zip Code 78599
7. Business Phone No. 956-969-4507	Alternate Phone No. 956-607-7487	E-mail Address N_QUINTANILLA@YAHOO.COM	

OWNER INFORMATION

8. Type of Owner		
☒ Individual	☐ Corporation	☐ City/County/University
☐ Partnership	☐ Limited Liability Company	☐ Other _____
☐ Limited Partnership	☐ Joint Venture	
☐ Limited Liability Partnership	☐ Trust	
9. Owner of Business /Applicant (Name of Corporation, LLC, etc.) RICARDO R GUERRA (WESTGATE MEAT MARKET)		

PRIMARY CONTACT PERSON

The primary contact person should be a person who can answer questions TABC may have about the application. The contact phone and email are mandatory and must be active and updated regularly. If additional information is needed, it will be requested from this contact person. Delays in responding to requests may delay the processing and approval of your permit/license.

10. Contact Person: RICARDO GUERRA	Relation to Business: OWNER
Phone (mandatory): 956-607-7487	Email (mandatory): N_QUINTANILLA@YAHOO.COM

TABC DATESTAMP


11. Is the applicant, a veteran-owned business? ☐ Yes ☒ No			
12. Is the applicant, a Historically Underutilized Business (HUB)? ☐ Yes ☒ No			
13. As indicated on the chart, enter the individuals that pertain to your business type: (For additional space, use Form L-OIC)			
Individual/Individual Owner		Limited Liability Company/All Officers or Managers	
Partnership/All Partners		Joint Venture/Venturers	
Limited Partnership/All General Partners		Trust/Trustee(s)	
Corporation/All Officers		City, County, University/Official	
Last Name GUERRA	First Name RICARDO	MI R	Title OWNER
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title

MEASUREMENT INFORMATION	
Section 109.31 et. seq.	
14. Will your business be located within 300 feet of a church or public hospital? ☐ Yes ☒ No	
NOTE: For churches or public hospitals measure from front door to front door, along the property lines of the street fronts and in a direct line across intersections.	
15. Will your business be located within 300 feet of any private/public school? ☐ Yes ☒ No	
NOTE: For private/public schools measure in a direct line from the nearest property line of the school to the nearest property line of the place of business, and in a direct line across intersections.	
NOTE: If located on or above the fifth story of a multistory building: measure in a direct line from the property line of the private/public school to property line of your place of business in a direct line across intersections vertically up the building at the property line to the base of the floor on which your business is located.	
16. Will your business be located within 1,000 feet of a private school? ☐ Yes ☒ No	
17. Will your business be located within 1,000 feet of a public school? ☐ Yes ☒ No	
PACKAGE STORE ACQUISITIONS ONLY	
18. Has the business being acquired been in operation in the same county for more than one year before the acquisition? ☐ Yes ☒ No	
If Yes, provide permit number for existing package store: _____	
If No, this does not qualify as an acquisition, and will be considered a new location.	
ALL APPLICANTS	
19. CHECK HERE IF NOT IN CITY LIMITS ☐	
I, the applicant, have confirmed the location is not located within city limits, therefore city certifications are not required.	
COMPLETE THE FOLLOWING CHECKLIST BEFORE SUBMITTING YOUR APPLICATION	
Per Sec. 102.01, a tied house is defined as any overlapping ownership between those engaged in the alcoholic beverage industry at different levels of the three-tier system. No person having an interest in a permit issued by TABC may secure or hold, directly or indirectly, an ownership interest in a business on a different level.	
All required forms have been completed. I have reviewed all forms to ensure they are complete. I have obtained all required local and state certifications (pages 3-4). All application packets have been notarized. Phone numbers and email address for Contact Person are up to date. All additional documentation as required by the application packets is attached If required, out of state criminal history checks are attached (PHS #7). Certification of publication in local newspaper has been completed (page 5). A copy of the newspaper publication is attached (page 5).	☒ Yes ☐ No ☒ Yes ☐ No ☐ Yes ☐ No ☐ Yes ☐ No ☐ Yes ☐ No ☐ Yes ☐ No ☐ Yes ☐ No ☐ Yes ☐ No ☐ N/A ☐ Yes ☐ No ☐ N/A ☐ Yes ☐ No ☐ N/A

WARNING AND SIGNATURE	If Applicant Is/Must Sign	
	Individual/Individual Owner	Corporation/Officer
	Partnership/Partner	Limited Liability Company/ Officer or Manager
	Limited Partnership/General Partner	


WARNING: Section 101.69 of the Texas Alcoholic Beverage Code states: "...a person who knowingly makes a false statement or false representation in an application for a permit or license or in a statement, report, or other instrument to be filed with the Commission and required to be sworn commits an offense punishable by imprisonment in the Texas Department of Criminal Justice for not less than 2 nor more than 10 years."


BY SIGNING YOU ARE SWEARING TO ALL INFORMATION AND ATTACHMENTS TO THIS PACKET.

PRINT NAME RICARDO R GUERRA **SIGN HERE** 

TITLE OWNER

Before me, the undersigned authority, on this 7th day of January, 2021, the person whose name is signed to the foregoing application personally appeared and, duly sworn by me, states under oath that he or she has read the said application and that all the facts therein set forth are true and correct.

SIGN HERE  **NOTARY PUBLIC**

SEAL 

CERTIFICATE OF CITY SECRETARY FOR P, Q, BF & BQ
Section 11.37 & 61.37

Not later than the 30th day after the date a prospective applicant for a license or permit requests certification, the city secretary or clerk shall certify whether the location or address given in the request is in a wet area and whether the sale of alcoholic beverages for which the license or permit is sought is prohibited by ordinance.

I hereby certify on this _____ day of _____, 20____, that the location for which the license/permit is sought is inside the boundaries of this city or town, in a "wet" area for such license/permit, and not prohibited by charter or ordinance in reference to the sale of such alcoholic beverages.

OR

☐ I hereby refuse on this _____ day of _____, 20____ to certify this location.

SIGN HERE _____, TEXAS
City Secretary/Clerk City

SEAL

CERTIFICATE OF COUNTY CLERK FOR P, Q & BF
Section 11.37 & 61.37

Not later than the 30th day after the date a prospective applicant for a license or permit requests certification, the county clerk shall certify whether the location or address given in the request is in a wet area and whether the sale of alcoholic beverages for which the license or permit is sought is prohibited by order.

I hereby certify on this _____ day of _____, 20____, that the location for which the license/permit is sought is in a "wet" area for such license/permit, and is not prohibited by any valid order of the Commissioner's Court.

OR

☐ I hereby refuse on this _____ day of _____, 20____ to certify this location.

SIGN HERE _____ COUNTY
County Clerk

SEAL

CERTIFICATE OF COUNTY CLERK FOR BQ

Section 11.37 & 61.37

Not later than the 30th day after the date a prospective applicant for a license or permit requests certification, the county clerk shall certify whether the location or address given in the request is in a wet area and whether the sale of alcoholic beverages for which the license or permit is sought is prohibited by order.

I hereby certify on this _____ day of _____, 20____, that the location for which the license/permit is sought as the place of business is in a "wet" area and is not prohibited by any valid order of the Commissioner's Court for a Wine and Beer Retailer's Off-Premise Permit.

Most current election for given location was held for:

- ☐ legal sale of all alcoholic beverages for off-premise consumption
- ☐ legal sale of all alcoholic beverages
- ☐ legal sale of all alcoholic beverages except mixed beverages
- ☐ legal sale of all alcoholic beverages including mixed beverages
- ☐ legal sale of mixed beverages
- ☐ legal sale of mixed beverages in restaurants by food and beverage certificate holders
- ☐ legal sale of wine on the premises of a holder of a winery permit
- ☐ legal sale of beer/wine (17%) on-premise or beer/wine off-premise **AFTER** Sept. 1, 1999
- ☐ legal sale of beer/wine (14%) on-premise or beer/wine off-premise **BEFORE** Sept. 1, 1999

OR

☐ I hereby refuse on this _____ day of _____, 20____ to certify this location.

SIGN

HERE _____

County Clerk

_____ COUNTY

S E A L

COMPTROLLER OF PUBLIC ACCOUNTS CERTIFICATE

Sections 11.46(b) & 61.42(b)

This is to certify on this _____ day of _____, 20____, the applicant holds or has applied for and satisfies all legal requirements for the issuance of a Sales Tax Permit under the Limited Sales, Excise and Use Tax Act or the applicant as of this date is not required to hold a Sales Tax Permit.

Sales Tax Permit Number _____ Outlet Number _____

Print Name of Comptroller Employee _____

Print Title of Comptroller Employee _____

SIGN

HERE _____

FIELD OFFICE _____

S E A L

PUBLISHER'S AFFIDAVIT (FOR BQ, BF, P & Q)		
Sections 11.39 & 61.38		
Name of newspaper		ATTACH PRINTED COPY OF THE NOTICE HERE <u>Hover over to see example</u>
City, County		
Dates notice published in daily/weekly newspaper (MM/DD/YYYY)		
<i>Publisher or designee certifies attached notice was published in newspaper stated on dates shown.</i>		
Signature of publisher or designee		
Sworn to and subscribed before me on this date		
Signature of Notary Public		
SEAL		



**TEXAS ALCOHOLIC
BEVERAGE COMMISSION**
Texans Helping Businesses & Protecting Communities

OWNERSHIP INFORMATION
Continued for Prequalification Packet

L-OIC
(10/2020)

LOCATION INFORMATION			
1. Trade Name of Location WESTGATE MEAT MARKET			
2. Location Address 2720 N WESTGATE DR			
City WESLACO	County HIDALGO	State TX	Zip Code 78599
OWNER INFORMATION			
3. Type of Owner			
☒ Individual ☐ Corporation ☐ City/County/University ☐ Partnership ☐ Limited Liability Company ☐ Other _____ ☐ Limited Partnership ☐ Joint Venture ☐ Limited Liability Partnership ☐ Trust			
Last Name GUERRA	First Name RICARDO	MI R	Title OWNER
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title
Last Name	First Name	MI	Title

City of Weslaco

"The City on the Grow"



David Suarez, Mayor
Leo Muñoz, Mayor Pro-Tem, District 1
Greg Kerr, Commissioner, District 2
Jose "J.P." Rodriguez, Commissioner, District 3
Adrian Farias, Commissioner, District 4
Letty Lopez, Commissioner, District 5
Josh Pedraza, Commissioner, District 6

Mike R. Perez, City Manager

PLANNING DEPARTMENT

January 22, 2021

Legal Notice

Dear Occupant:

The Weslaco Planning and Zoning Commission will hold a public hearing on Wednesday, February 3, 2021, and the City Commission will hold a public hearing on February 16, 2021 at 5:30 p.m. at the City Hall Legislative Chambers located at 255 South Kansas Avenue and via zoom to consider the following request:

Telephonic conferencing capabilities will be utilized to allow member of the public to participate remotely via Toll Free Dial In Number: +1 346 248 7799; Meeting ID: 832 0582 2197

Members of the public who wish to participate in Public Hearing on an agenda item must send their name, address and phone number via email to karevalo@weslacotx.gov by 12:00 pm on February 3, 2021. A staff member will contact you with instructions via phone call to address your public comment.

CONDITIONAL USE PERMIT REQUEST:

Ricardo Guerra is requesting a Conditional Use Permit to obtain an Off-Premise Wine and Beer Retailer's Permit at 2720 N Westgate, also being Lot 1 & 2, Block 5, Sun Country Estates Subdivision, Hidalgo County, and Texas.

The public is hereby invited to attend and express their support or opposition to the request. You may also file a written notice supporting or protesting this action. For more information please call the Planning Department at (956) 447-3403.


Si desea información en español, por favor llame al departamento de Planeación de la ciudad de Weslaco, (956) 447-3403.

Sincerely,

Rebekah de la Fuente, CFM
Planning Director

CITY OF WESLACO

Engineering Department



Ricardo R. Guerra
2720 North Westgate Drive
Sun Country Estates Unit No2,
Lots 1 & 2, BLK 5
LOT 13, BLOCK 161, F.T. 141

Purpose for the Conditional Use Permit request
Existing zoning: R-1
Existing land use: One Family Dwelling
CUP request: Meat Market \ Convenience Store



City of Weslaco Code Enforcement Dept.

JAN 21, 2021

GUERRA HERMELINDA 6700 N MILE 3 1/2 W WESLACO TX 78596-1479	S6900-00-005-0001-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 1 BLK 5 0	L: 13320 B: 0
GUERRA HERMELINDA 2720 N WESTGATE DR WESLACO TX 78599-3875	S6900-00-005-0002-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 2 BLK 5	L: 21000 B: 12814
CARDOSA SILVIO HECTOR & 2710 N WESTGATE DR WESLACO TX 78599-3875	S6900-00-005-0003-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 3 BLK 5 0	L: 14400 B: 38459
AGUILAR ELIZABETH 1610 JUDI ST WESLACO TX 78599-4070	S6900-00-005-0004-00 SUN COUNTRY ESTATES UNIT NO. 2 L OTS 4 & 5 BLK 5 0	L: 30600 B: 39615
SIFUENTES EMMA 1609 EDNA ST WESLACO TX 78599-4095	S6900-00-005-0006-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 6 BLK 5 0	L: 15840 B: 38290
SALINAS JESUS E & SAN JUANITA 1607 EDNA ST WESLACO TX 78599-4095	S6900-00-005-0007-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 7 BLK 5 0	L: 15840 B: 21048
GONZALEZ JAVIER & DALIA 1509 EDNA ST WESLACO TX 78599-4138	S6900-00-005-0008-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 8 BLK 5 0	L: 14400 B: 0
TYRAQ FAMILY LP 2228 MARTHA'S LN PALMHURST TX 78573-0176	S6900-00-005-0009-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 9 BLK 5 1201 EDNA ST	L: 15840 B: 0
TYRAQ FAMILY LP 2228 MARTHA'S LN PALMHURST TX 78573-0176	S6900-00-005-0010-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 10 BLK 5 1201 EDNA ST	L: 15840 B: 97160
AGUILAR ADAM A ETAL 1610 JUDI ST WESLACO TX 78599-4070	S6900-00-005-0011-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 11 BLK 5 0	L: 15840 B: 6752
CUELLAR GUADALUPE & ANTONIA 1608 JUDI ST WESLACO TX 78599-4070	S6900-00-005-0012-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 12 BLK 5 0	L: 15840 B: 13044
ROBLEDO JUAN 2629 GRANADA WESLACO TX 78599-4540	S6900-00-005-0013-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 13 BLK 5 0	L: 14400 B: 0

City of Weslaco Code Enforcement Dept.


JAN 21, 2021

GARCIA ADELINA 900 W 7TH ST WESLACO TX 78596-6702	S6900-00-005-0014-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 14 BLK 5 1602 JUDI ST	L: 15840 B: 22370
GARCIA ADELINA 900 W 7TH ST WESLACO TX 78596-6702	S6900-00-005-0015-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 15 BLK 5 1602 JUDI ST	L: 15840 B: 5217
AGUILAR JUAN R ETAL 1610 JUDI ST WESLACO TX 78599-4070	S6900-00-007-0001-00 SUN COUNTRY ESTATES UNIT NO. 2 L OTS 1 & 2 BLK 7 0	L: 50400 B: 40389
GUERRA SERGIO & DENYS 1609 JANIE ST WESLACO TX 78599-4182	S6900-00-007-0003-00 SUN COUNTRY ESTATES UNIT NO. 2 L OTS 3 & 4 BLK 7 0	L: 47040 B: 14045
REYNA ROSBEL & REYNA NELIA S 1610 EDNA ST WESLACO TX 78599-4155	S6900-00-007-0008-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 8 BLK 7 0	L: 15840 B: 19158
MARTINEZ LEONARDO & IRMA 1608 EDNA ST WESLACO TX 78599-4155	S6900-00-007-0009-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 9 BLK 7 0	L: 15840 B: 25909
HINOJOSA LORENZO 1604 EDNA ST WESLACO TX 78599-4155	S6900-00-007-0010-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 10 BLK 7 0	L: 14400 B: 14840
HINOJOSA LORENZO 1604 EDNA ST WESLACO TX 78599-4155	S6900-00-007-0011-00 SUN COUNTRY ESTATES UNIT NO. 2 L OT 11 BLK 7 0	L: 15840 B: 0
DE LEON JESUS PO BOX 8308 WESLACO TX 78599-8308	W3800-00-143-0000-00 WEST TRACT FT 143 13.79AC-15AC E XC 1.0-IMPS 12.37AC NET	L: 253585 B: 0
DE LEON JESUS PO BOX 8308 WESLACO TX 78599-8308	W3800-00-143-0000-01 WEST TRACT 1.0AC-15.79AC AN IRR TR-E534.40'-N91.86'-S721.07' FT	L: 20500 B: 27944



Planning & Zoning Commission Standardized Agenda Request Form

Date of Meeting: February 3, 2021	Agenda Item No. (to be assigned by PCE): V. A.
From: Rebekah de la Fuente, Planning Director, on behalf of SWG Engineering, LLC.	
Subject/Agenda Item: Discussion and consideration for the Preliminary Plat for Pike District Subdivision– being 36.052 acres out of Farm Tract 163, West and Adams Tract Subdivision, Weslaco, Hidalgo County, Texas located approximately the southeast corner of W. Pike Blvd and Milanos Rd. Possible Action.	
Discussion/Overview: The proposed One hundred nineteen (119) lot subdivision is inside the City of Weslaco. This subdivision is being serviced with water by the City of Weslaco through an 8" waterline and sewer by the City of Weslaco services through a 6" sewer line. The property is within a Flood Zone "X".	
If item requires Publication Notice, provide date and periodical of publication; indicate if comments received from letters mailed to property owners: N/A	
Staff recommendation for Commission's Action: Staff recommends approval of Preliminary Plat.	
Additional Action Prompted: [X] Mayor's Signature [] Public Hearing [] Budget Amendment [] Resolution [] Ordinance – First Reading [] Ordinance – Final Reading	
Advisory Review, (if any): (name of board/committee, date of action, recommendation): N/A	
If item previously considered, provide date and action by Commission: N/A	
Attachments,(if any): Application for Subdivision platting, Staff's comments, Drainage Report, Subdivision plat and Utility layout.	
Responsibilities upon Commission's Action: Planning staff will advise applicant.	



SUBDIVISION PLATTING APPLICATION

The Planning & Zoning Commission meets every 1st Wednesday of each month at 5:30 pm.

The City Commission meets every 1st and 3rd Tuesday of each month at 5:30 pm

FILE NO. _____

This form shall be completed by the Property Owner or Applicant and submitted to the Planning Department along with the required number of copies of the respective plat, review fee and all other required information listed below and in the Subdivision Ordinance. The submittal of an application does not constitute acceptance for processing until the staff reviews and determines the application is complete.

STAFF USE ONLY

☐ Single Lot Variance ☐ Minor Plat ☐ Planned Unit Development ☐ Standard Subdivision

GENERAL INFORMATION

Name of Subdivision: Pike District Subdivision

Location: Southwest Corner of W. Pike Blvd. (Mile 8 North) and Milanos Rd (Mile 6 1/2 West Rd.)

Legal Description: A tract of land containing 36.092 Acres situated in the City of Weslaco, Hidalgo County, Texas being a part or portion of Farm Tract 163, Block 178, The West and Adams Tracts.

Is subdivision inside city limits? ☒ YES ☐ NO

If subdivision is in the ETJ, indicate? ☐ 3.5 Mile ☐ 5 Mile

If no submit letter of Annexation (Contiguous or Consensual)

Existing Zoning: R-I

Existing Land Use: Vacant Proposed Land Use: One Family Dwelling

Number of Lots Proposed: 113 Gross Acreage: 36.092

Title Report Submitted: ☐ YES ☒ NO

OWNER INFORMATION

Owner's Name: ZAIDA LLC Telephone: (956) 647-8409

Address: 230 W. Pile Suite 105

Fax: _____

City: Weslaco

State: Tx

Zip: 78596

E-mail: _____

ENGINEER INFORMATION

Name: SWG Engineering LLC

Telephone: (956) 968-2194

Address: 611 Bill Summers Intl. Blvd.

Fax: (956) 968-8300

City: Weslaco

State: Tx

Zip: 78596

E-mail: jreyes@siglerwinstongreenwood.com

UTILITY PROVISIONS

Will proposed subdivision connect to:

☒ YES ☐ NO Water Provision: NAWSC

☒ YES ☐ NO Wastewater Provision: City of Weslaco

☒ YES ☐ NO Electric Company: AEP

☒ YES ☐ NO Phone Utility _____	☒ YES ☐ NO Gas Utility _____	☒ YES ☐ NO Cable Utility _____
---	---	---

Proposed subdivision is in the following districts:

☒ YES ☐ NO Drainage District <u>HCDD#1</u>	☒ YES ☐ NO Irrigation District <u>HCCID#9</u>
---	--

Has the property been assessed as flat rate irrigable property: ☐ YES ☐ NO

Have Water Rights been conveyed to City/Water Supplier? ☐ YES ☐ NO

(Attach written proof of such assessment or that it has never been assessed as such a property) If **YES**, attach an estimate from the irrigation district of the proportional water rights for the subdivision as calculated under Texas Water Code § 49.505.

SUBMITTALS REQUIRED FOR MINOR PLAT REVIEW

_____ **Two (2)** sets of plats **folded and stapled** (24 x 36) and forward a copy in PDF format to mhinojosa@weslacotx.gov & rdelafuente@weslacotx.gov

_____ **\$355.00** Planning Review fee

_____ One 11" X 17" reduced copy of plat

_____ Plat Layout

_____ Existing & Proposed Easements

_____ Existing & Proposed ROW

_____ Existing & Proposed Drainage Easements

_____ Contours

_____ Flood Zones

_____ Adjoiners

_____ Existing street names

_____ Drainage plans and calculations with engineer's seal

_____ Elevations

_____ Flood directional arrows

_____ Detention areas

_____ Street names

_____ Proof of ownership of the property

_____ If septic tank system required, submit soil evaluation report

_____ Water Rights associated with the property

_____ Tax Receipt for all taxing entities showing that taxes are paid in full

SUBMITTALS REQUIRED FOR PRELIMINARY (P & Z)

✓ _____ **Twelve (12)** sets of preliminary plat **folded and stapled** (24 x 36) and forward a copy in PDF format to mhinojosa@weslacotx.gov & rdelafuente@weslacotx.gov

✓ _____ **\$350.00** (one time fee for preliminary and final plat)

✓ _____ One 11" X 17" reduced copy of plat

✓ _____ Plat Layout

✓ _____ Existing & Proposed Easements

✓ _____ Existing & Proposed ROW

✓ _____ Existing & Proposed Drainage Easements

- ☒ Contours
- ☒ Flood Zones
- ☒ Adjoiners
- ☒ Existing & Proposed street names
- ☒ Utility Layout
 - ☒ Existing & Proposed Utilities
 - ☒ Proposed Fire Hydrants
 - ☒ Adjoiners
 - ☒ Street names
- ☒ Drainage plans and calculations with engineer's seal
 - ☒ Elevations
 - ☒ Flood directional arrows
 - ☒ Detention areas
 - ☒ Street names
- ☐ Proof of ownership of the property
- ☐ If septic tank system required, submit soil evaluation report
- ☐ Water Rights associated with the property
- ☐ Tax Receipt for all taxing entities showing that taxes are paid in full
- ☐ 7 Number of fire hydrants proposed for subdivision
- ☒ Trip Generation Worksheet

SUBMITTALS REQUIRED FOR FINAL (P & Z) **Will not apply to Single Lot Variance**

- ☐ Twelve (12) sets of plans **FOLDED & STAPLED** (24 x 36) & PDF copy **with all corrections**
- ☐ Plats to be sealed by Professional Engineer
- ☐ Approved Drainage Report
- ☐ Traffic Impact Analysis (If required)

SUBMITTALS REQUIRED FOR FINAL (City Commission)

- ☐ One set of 8 ½ x 11 of plat and utilities with all corrections done

SUBMITTALS REQUIRED FOR PRE-CONSTRUCTION MEETING

- ☐ Seven (7) full sets of construction plans 24 x 36 and one (1) 11 x 17 with plan & profile.
- ☐ Engineering cost estimates for 3% geotechnical testing fees and 2% inspection fees
- ☐ Notice of Intent
- ☐ SW3P

SUBMITTALS REQUIRED FOR RECORDING OR HIDALGO COUNTY PLANNING

- ☐ Electronic file of final plat and as-builds
- ☐ Reproducible plat to be recorded with all required signatures
- ☐ 3% geotechnical testing fees or negotiated Material Testing fee by City, whichever is higher
- ☐ 2% inspection fee
- ☐ Park Fees
- ☐ Checks or Receipts: HCCID #9; HCDD #1; County Clerk
- ☐ Tax certificates
- ☐ Memo from engineering inspector releasing subdivision
- ☐ Water Rights associated with the property dedicated and assigned to City of Weslaco or payment of fees sufficient to meet the needs necessitated and attributable to development
- ☒ 30 Year Water and 30 Year Sewer Service Agreements
- ☐ Park dedication/Fees in lieu of

SUBMITTALS REQUIRED FOR RECORDING BY SECURITY

- ☐ Sealed engineering cost estimates
- ☐ Letter of Credit/Performance Bond/Escrow

** Any revisions requested would require resubmission of plats and reduced copy reflecting changes.

AUTHORIZATION AND ACKNOWLEDGEMENTS

I certify that I am the actual owner of the property described above and this application is being submitted with my consent (include corporate name if applicable); and the following person listed below is my authorized agent to act on my behalf.

I certify that the above information is correct and complete to the best of my knowledge. I understand that I must comply with all applicable local, state, and federal regulations.

Owner Printed Name: _____

Owner Signature: _____ Date: _____

SWG Engineering LLC _____ is the authorized agent

Authorized Agent Signature: Jose G. Reyes, P.E. Date: January 27, 2021

Authorized Agent Printed Name: Jose G. Reyes, P.E.

THIS PAGE FOR STAFF USE ONLY

Date Received: _____ Received By: _____ Date Paid _____

P & Z Commission Approval on Preliminary Plat: _____

P & Z Commission Approval on Final Plat: _____

City Commission Approval on Final Plat: _____

Preconstruction Meeting Date: _____

Date Recorded: _____ Instrument No. _____

General Comments: _____

SWG Engineering

Hidalgo County Drainage District No. 1

Drainage Report

Weslaco – Pike District Subdivision

Hidalgo County, Texas

Prepared By:

SWG Engineering, LLC

611 Bill Summers Intl. Blvd.


Weslaco, Texas 78596

Tel: 956-968-2194

Fax: 956-968-8300

sergio@siglerwinstongreenwood.com

1/14/2021



[Handwritten signature] P.E.
JAN. 14. 2021

COVER SHEET	1
INDEX	2
PROJECT LOCATION	3
FLOOD PLAIN	3
SOIL CONDITIONS	3
EXISTING CONDITIONS	3
PROPOSED CONDITIONS	3
LOCATION MAP	4
HYDRAULIC CALCULATIONS	5
"C" VALUES FOR RATIONAL METHOD	6
RAINFALL INTENSITY FOR HIDALGO COUNTY	7
FLOOD PLAIN ATTACHMENTS	8
SOIL CONDITION ATTACHMENT	9

**DRAINAGE REPORT
For
PIKE DISTRICT SUBDIVISION**

I. Project Location

This project involves the development of a 35.21 acre tract of land for residential use. The site is located in the city of Weslaco, Hidalgo County and lies on the southwest intersection of W Pike Blvd (Mile 8 North Rd.) and N Milano Rd (Mile 6 1/2 West Rd.) just outside of the city limits. The proposed subdivision is comprised of 113 lots for a total of a 35.21 acre tract out of West tract, Hidalgo County, Texas.

II. Flood Plain

The area is considered to be under an unincorporated area determined by FEMA Flood Insurance Rate Map, Community Panel No. 480334 0450 C, and Map Revised June 6, 2000. The project area is under Zone "X", which is described as "Areas of 500-year flood; areas of 100-year flood with average depths of less than 1 foot or with drainage areas less than 1 square mile and areas protected by levees from 100-year flood".

III. Soil Conditions

According to the Soil Survey Report prepared for Hidalgo County by the U.S.D.A. Soil Conservation Service, the area is composed of three types of soil: Hidalgo fine sandy loam (0 to 1 percent slopes), Hidalgo fine sandy loam (1 to 3 percent slopes), and Hidalgo sandy clay loam (0 to 1 percent slopes). The predominant soil type being Hidalgo clay loam, is listed in Hydrological Group B. See attached Soil Survey of Hidalgo County, Texas.

IV. Existing Conditions


Existing runoff is by surface flow in a southwestern direction and has a runoff of **24.25 cfs** during the **10-yr** storm frequency as per attached calculations. The total impermeable area is approximately 0 square feet and the total permeable area is **1,533,748 sf²**. Due to no existing development, an existing weighted runoff coefficient of C = 0.2 was calculated.


V. Proposed Conditions

Subject tract of land will be developed into 113 lots that will serve as a residential subdivision. One of the lots will be dedicated for a detention pond. Proposed runoff after development is **114.9 cfs**, during the **50-year** storm frequency, which is an increase of **90.65 cfs**. The proposed drainage for Pike District Subdivision consists of surface runoff from future development into the street and green areas. The total impermeable area is approximately **1,454,904 sf²** and the total permeable area is **78,408 ft²**. A

weighted runoff coefficient of $C = 0.59$ was calculated. For a **50-year storm frequency**, a peak detention volume is approximately **253,831 ft³ or 5.83 Acre-ft**. Please refer to attached drainage calculations. At time of improvements the storm water runoff from the improved area shall be discharged in a southwestern direction where it will be discharged into a proposed detention pond on the southeast corner of subdivision. The runoff shall be directed into an existing manhole along Milano's Rd. (Mile 6 ½ West Rd.), via 24" RCP, connected to an existing storm system, that will carry the storm water via 42" RCP to drain ditch 37D1, owned by HCCID#9. The detention pond is designed in order to detain a volume of **363,290 ft³**, which will be able to hold a 100 year frequency.

The drainage calculations are attached.


Jose G. Reyes, P.E.
January 14, 2021



Weslaco – Pike District Subdivision

Hidalgo County Drainage District No. 1
“C” Values for Rational Method

Type of Drainage Area	Runoff Coefficient
Residential Districts:	
Single Family (Lots less than ¼ acre)	0.30 – 0.50
Multi - Family (Less than 20 DU/AC)	0.40 – 0.60
Multi - Family (Greater than 20 DU/AC)	0.60 – 0.75
Business District:	
Downtown areas	0.70 – 0.95
Neighborhood areas	0.30 – 0.70
Industrial Districts:	
Light Areas	0.30 – 0.80
Heavy Areas	0.60 – 0.90
Railroad Yard Areas:	0.30 – 0.40
Park:	0.10 – 0.25
Unimproved Areas:	
Sand or sandy loam soil, 0-3%	0.15 – 0.20
Sand or sandy loam soil, 3-5%	0.20 – 0.25
Black or loessial soil, 0-3%	0.18 – 0.25
Black or loessial soil, 3-5%	0.25 – 0.30
Black or loessial soil, >5%	0.70 – 0.80
Deep sand area	0.05 – 0.15
Steep grassed slopes	0.70
Street:	
Asphalt	0.85 – 0.95
Concrete	0.90 – 0.95
Drives & Walks:	
Concrete	0.75 – 0.95

Last Updated: 1/13/2021

Detention Calculator

10-yr release
e= 0.8599
b= 116.24
d= 14.33

50 yr Storm
Title: SWG# 20-135
35.21 Ac Mitigation Area
City of Weslaco, TX

Required Volume:
Req'd Volume 5.83 ac.ft

EXISTING DATA


Total Area 35.21 acre
Overland Flow Length - "L" 1100.00 LF
Existing Time of Concentration - "Tov" (grass) 45.55 % composition? 100%
Existing Time of Concentration - "Tov" (pavmt) 0.00 % composition? 0%
Total Existing Time of Concentration - "Tov" 45.55 minutes
Existing Runoff Coefficient - "C" 0.20
Intensity of Rainfall - "I" 3.44 in/hr
Existing - "Q" 24.25 cfs

e= 0.8613
b= 170.66
d= 16.71

PROPOSED IMPROVEMENTS

Total Area 35.21 acre
Overland Flow Length - "L" 1100.00 LF
Proposed Time of Concentration - "Tov" (grass) 33.71 % composition? 74%
Proposed Time of Concentration - "Tov" (pavmt) 2.92 % composition? 26%
Total Proposed Time of Concentration - "Tov" 36.63 minutes
Proposed Runoff Coefficient - "C" 0.59
Intensity of Rainfall - "I" 5.55 in/hr
Proposed - "Q" 114.90 cfs

Time		I	Q in	V in	Q out	V out	Req'd V	Req'd V	
min	hr	in/hr	ft ³ /s	ft ³	ft ³ /s	ft ³	ft ³	ac-ft	
36.63	0.61	5.55	114.90	252549	24.25	53306	199243	4.57	
46.63	0.78	4.79	99.09	277264	24.25	60581	216683	4.97	
56.63	0.94	4.22	87.34	296783	24.25	67857	228927	5.26	
66.63	1.11	3.78	78.24	312786	24.25	75132	237654	5.46	
76.63	1.28	3.43	70.96	326277	24.25	82408	243870	5.60	
86.63	1.44	3.14	65.01	337898	24.25	89683	248215	5.70	
96.63	1.61	2.90	60.03	348079	24.25	96959	251120	5.76	
106.63	1.78	2.70	55.82	357122	24.25	104234	252888	5.81	
116.63	1.94	2.52	52.19	365247	24.25	111510	253737	5.83	
126.63	2.11	2.37	49.04	372616	24.25	118785	253831	5.83	High Point
136.63	2.28	2.24	46.27	379354	24.25	126061	253294	5.81	
146.63	2.44	2.12	43.82	385558	24.25	133336	252222	5.79	
156.63	2.61	2.01	41.64	391305	24.25	140612	250693	5.76	
166.63	2.78	1.92	39.67	396655	24.25	147887	248768	5.71	
176.63	2.94	1.83	37.90	401660	24.25	155163	246498	5.66	
186.63	3.11	1.75	36.29	406361	24.25	162438	243923	5.60	
196.63	3.28	1.68	34.82	410793	24.25	169714	241079	5.53	
206.63	3.44	1.62	33.47	414984	24.25	176989	237995	5.46	



Jose G. Reyes, Jr.
P.E.
Jan. 14, 2021

Existing Runoff Coef. Calculation:

Total Area =		35.2 acres	<u>0.20</u>
Impermeable Area =	0%	0.0 acres	0.9
Pavement Area =	0%	0.0 acres	0.95
Permeable Area =	100%	35.2 acres	0.2

Future Runoff Coef. Calculation:

Total Area =		35.2 acres	<u>0.59</u>
Impermeable Area =	26%	9.1 acres	0.9
Permeable Area =	5%	1.8 acres	0.2
Residential Area =	69%	24.3 acres	0.5

Elevations:

High =	88.68 ft
Low =	81.5 ft

Average Slope (Adjusted) = 0.00703

K= 0.828 *std coefficient*

N grass= 0.4 *unitless*

N pavement= 0.02 *unitless*

Rainfall Intensity-Duration-Frequency Coefficients for Texas

Based on United States Geological Survey (USGS) Scientific Investigations Report 2004-5041
"Atlas of Depth-Duration Frequency of Precipitation Annual Maxima for Texas"

1. Select English or SI Units

2. Select or Enter a County

3. Enter a Time of Conc.


Select Units

Coefficient	50% (2-year)	20% (5-year)	10% (10-year)	4% (25-year)	2% (50-year)	1% (100-year)
e	0.8645	0.8647	0.8599	0.8572	0.8613	0.8619
b (in.)	72.40	100.21	116.24	140.47	170.66	201.07
d (min)	12.92	13.90	14.33	15.32	16.71	18.00


Intensity (in./hr) 2.49 3.39 3.98 4.78 5.58 6.43


(Spreadsheet Release Date: August 31, 2015; data table reshuffle by Asquith July 14, 2016)


Attachments



Z:\DRAFTING\MANUEL\ACAD\20-135-PIKE DIST SUBD-TANUS\PIKE DIST SUBD-12-22-20 1/14/2021 9:47 AM







Produced by the United States Geological Survey

Topographic Survey of 1911 (1911-1912) Project and
1:50,000 Scale of 1911 (1911-1912) Project and
1:50,000 Scale of 1911 (1911-1912) Project and

Legend
1:50,000 Scale
1:50,000 Scale
1:50,000 Scale



SCALE 1:24,000



CONTOUR INTERVAL 10 FEET

VERTICAL DATUM 1988

This map was produced in conformance with the
National Map Accuracy Standards, 1994
A revision to the 1994 edition of the standards is in progress.



1	2	3
4	5	6
7	8	9

ROAD CLASSIFICATION	
Expressway	Local Road
Secondary Road	US Route
Ramp	State Road

DONNA, TX
2019



United States
Department of
Agriculture


NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for Hidalgo County, Texas

Pike District Subdivision



December 28, 2020

Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface.....	2
How Soil Surveys Are Made.....	5
Soil Map.....	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
Hidalgo County, Texas.....	13
25—Hidalgo fine sandy loam, 0 to 1 percent slopes.....	13
26—Hidalgo fine sandy loam, 1 to 3 percent slopes.....	14
28—Hidalgo sandy clay loam, 0 to 1 percent slopes.....	15
References.....	18

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.


After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

Custom Soil Resource Report


identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



Custom Soil Resource Report



Custom Soil Resource Report

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
25	Hidalgo fine sandy loam, 0 to 1 percent slopes	2.9	8.8%
26	Hidalgo fine sandy loam, 1 to 3 percent slopes	0.8	2.5%
28	Hidalgo sandy clay loam, 0 to 1 percent slopes	29.8	88.7%
Totals for Area of Interest		33.6	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or

Custom Soil Resource Report

landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Custom Soil Resource Report

Hidalgo County, Texas

25—Hidalgo fine sandy loam, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2sxn
Elevation: 20 to 500 feet
Mean annual precipitation: 20 to 27 inches
Mean annual air temperature: 72 to 74 degrees F
Frost-free period: 300 to 365 days
Famland classification: Prime farmland if irrigated

Map Unit Composition

Hidalgo and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hidalgo

Setting

Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Calcareous loamy alluvium

Typical profile

Ap - 0 to 17 inches: fine sandy loam
Bk1 - 17 to 28 inches: sandy clay loam
Bk2 - 28 to 38 inches: clay loam
Ck - 38 to 80 inches: clay loam

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 35 percent
Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Sodium adsorption ratio, maximum: 10.0
Available water capacity: Moderate (about 7.8 inches)

Interpretive groups

Land capability classification (irrigated): 2s
Land capability classification (nonirrigated): 2s
Hydrologic Soil Group: B
Ecological site: R083DY019TX - Gray Sandy Loam
Hydric soil rating: No

Custom Soil Resource Report

Minor Components

Willacy

Percent of map unit: 10 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Hydric soil rating: No

Brennan

Percent of map unit: 5 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R083EY023TX - Sandy Loam
Hydric soil rating: No

26—Hidalgo fine sandy loam, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2sxvp
Elevation: 20 to 500 feet
Mean annual precipitation: 20 to 27 inches
Mean annual air temperature: 72 to 74 degrees F
Frost-free period: 300 to 365 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Hidalgo and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hidalgo

Setting

Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Convex
Across-slope shape: Linear
Parent material: Calcareous loamy alluvium

Typical profile

Ap - 0 to 17 inches: fine sandy loam
Bk1 - 17 to 28 inches: sandy clay loam
Bk2 - 28 to 38 inches: clay loam
Ck - 38 to 80 inches: clay loam

Custom Soil Resource Report

Properties and qualities

Slope: 1 to 3 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 35 percent
Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Sodium adsorption ratio, maximum: 10.0
Available water capacity: Moderate (about 7.8 inches)

Interpretive groups

Land capability classification (irrigated): 2e
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: B
Ecological site: R083DY019TX - Gray Sandy Loam
Hydric soil rating: No

Minor Components

Willacy

Percent of map unit: 10 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Convex
Across-slope shape: Linear
Hydric soil rating: No

Brennan

Percent of map unit: 5 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Convex
Across-slope shape: Linear
Ecological site: R083EY023TX - Sandy Loam
Hydric soil rating: No

28—Hidalgo sandy clay loam, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2sxxv
Elevation: 20 to 500 feet
Mean annual precipitation: 20 to 27 inches
Mean annual air temperature: 72 to 74 degrees F
Frost-free period: 300 to 365 days
Farmland classification: All areas are prime farmland

Custom Soil Resource Report

Map Unit Composition

Hidalgo and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hidalgo

Setting

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Calcareous loamy alluvium

Typical profile

Ap - 0 to 17 inches: sandy clay loam

Bk1 - 17 to 28 inches: sandy clay loam

Bk2 - 28 to 38 inches: clay loam

Ck - 38 to 80 inches: clay loam

Properties and qualities

Slope: 0 to 1 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Negligible

*Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.57 to 1.98 in/hr)*

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum content: 35 percent

Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)

Sodium adsorption ratio, maximum: 10.0

Available water capacity: Moderate (about 7.8 inches)

Interpretive groups

Land capability classification (irrigated): 1

Land capability classification (nonirrigated): 2c

Hydrologic Soil Group: B

Ecological site: R083DY019TX - Gray Sandy Loam

Hydric soil rating: No

Minor Components

Raymondville

Percent of map unit: 7 percent

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Ecological site: R083DY025TX - Clay Loam

Hydric soil rating: No

Racombes

Percent of map unit: 6 percent

Landform: Terraces

Custom Soil Resource Report

Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R083DY025TX - Clay Loam
Hydric soil rating: No

Willacy

Percent of map unit: 2 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Hydric soil rating: No

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelpdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

Hidalgo County, Texas

157

TABLE 16.--ENGINEERING INDEX PROPERTIES
[Absence of an entry indicates that data were not estimated]

Map symbol and soil name	Depth	USDA texture	Classification		Percentage passing sieve number--				Liquid limit	Plasticity index
			Unified	AASHTO	4	10	40	200		
	In								Pct	
1.* Arents										
2----- Benito	0-7 7-65	Clay----- Clay-----	CH CH	A-7-6 A-7-6	100 100	100 100	100 100	95-100 95-100	75-94 75-94	48-64 48-64
3, 4----- Brennan	0-13 13-65	Fine sandy loam Sandy clay loam, loam.	SM, SM-SC, SC, CL	A-2-4, A-4 A-2-4, A-2-6, A-4, A-6	100 95-100	98-100 90-100	70-100 60-100	20-45 30-59	<30 22-39	NP-9 8-22
5----- Camargo	0-8 8-65	Silt loam----- Stratified silty clay loam to very fine sandy loam.	CL, CL-ML CL	A-6, A-4 A-6, A-7-6	100 100	100 100	95-100 95-100	70-100 70-100	20-35 30-45	4-16 11-25
6----- Camargo	0-8 8-65	Silty clay loam Stratified silty clay loam to very fine sandy loam.	CL CL	A-6, A-7-6 A-6, A-7-6	100 100	100 100	95-100 95-100	70-100 70-100	30-45 30-45	11-25 11-25
7----- Cameron	0-30 30-65	Silty clay----- Silt loam, loam	CH, CL CL	A-7-6 A-4, A-6	100 100	100 95-100	100 90-100	90-100 70-95	48-68 25-35	25-41 8-15
8----- Comitas	0-28 28-80	Loamy fine sand Fine sandy loam, sandy clay loam.	SM, SM-SC SM, SC, SM-SC	A-2-4 A-2-4, A-2-6, A-4, A-6	95-100 95-100	95-100 90-100	85-100 80-100	15-25 23-50	<25 <34	NP-4 NP-14
9----- Delfina	0-13 13-34 34-72	Loamy fine sand Sandy clay loam, clay loam. Sandy clay loam, fine sandy loam.	SM, SM-SC SC, CL SC	A-2-4, A-4 A-6, A-7-6 A-6, A-7-6	100 100 90-100	100 95-100 75-98	85-100 90-100 70-97	20-45 40-55 36-50	<25 31-48 30-46	NP-7 18-35 16-31
10, 11----- Delfina	0-13 13-34 34-72	Fine sandy loam Sandy clay loam, clay loam. Sandy clay loam, fine sandy loam.	SM-SC, SC, SM SC, CL SC	A-2-4, A-4 A-6, A-7-6 A-6, A-7-6	100 100 90-100	100 95-100 75-98	90-100 90-100 70-97	25-50 40-55 36-50	19-30 31-48 30-46	3-10 18-35 16-31
12----- Delmita	0-13 13-34 34-60	Loamy fine sand Sandy clay loam, fine sandy loam. Indurated-----	SM, SM-SC, SP-SM SC ---	A-2-4 A-2-4, A-2-6, A-4, A-6 ---	100 100 ---	95-100 100 ---	85-100 90-100 ---	11-25 30-50 ---	<25 27-39 ---	NP-7 8-18 ---
13.* Delmita-----	0-13 13-34 34-60	Fine sandy loam Sandy clay loam, fine sandy loam. Indurated-----	SM, SM-SC SC ---	A-2-4 A-2-4, A-2-6, A-4, A-6 ---	100 100 ---	100 100 ---	90-100 90-100 ---	20-35 30-50 ---	<27 27-39 ---	NP-7 8-18 ---

See footnote at end of table.

158

Soil survey

TABLE 16.--ENGINEERING INDEX PROPERTIES--Continued

Map symbol and soil name	Depth In	USDA texture	Classification		Percentage passing sieve number--				Liquid limit Pct	Plas- ticity index
			Unified	AASHTO	4	10	40	200		
13:*										
Randado-----	0-9	Fine sandy loam	SM, SM-SC	A-2-4	75-100	70-100	70-100	20-35	<25	NP-7
	9-16	Fine sandy loam, sandy clay loam.	SC, SM-SC, GC	A-2-4, A-2-6, A-4, A-6	65-100	60-100	60-100	25-50	25-34	7-14
	16-60	Cemented-----	---	---	---	---	---	---	---	---
14-----										
Falfurrias	0-80	Fine sand-----	SP-SM, SM	A-2-4, A-3	100	100	75-100	5-25	<25	NP-3
15-----										
Grulla	0-7	Clay-----	CL, CH	A-7-6	100	100	100	90-100	41-55	20-30
	7-65	Silty clay, clay	CH	A-7-6	100	100	100	90-100	52-66	28-39
16, 17, 18-----										
Hargill	0-18	Fine sandy loam	SC, SM-SC, SM	A-2-4	100	95-100	95-100	17-35	<30	NP-8
	18-63	Sandy clay loam	SC, CL	A-6	100	95-100	95-100	40-55	30-40	11-20
	63-80	Sandy clay loam	SC	A-2-4, A-2-6, A-4, A-6	85-100	80-100	75-100	34-50	28-39	9-18
19, 20-----										
Harlingen	0-8	Clay-----	CH	A-7-6	100	100	100	90-100	51-85	32-60
	8-35	Clay-----	CH	A-7-6	100	100	100	95-100	65-85	50-65
	35-72	Clay-----	CH	A-7-6	100	100	100	95-100	65-85	50-65
21:*										
Harlingen-----	0-8	Clay-----	CH	A-7-6	100	100	100	90-100	51-85	32-60
	8-35	Clay-----	CH	A-7-6	100	100	100	95-100	65-85	50-65
	35-72	Clay-----	CH	A-7-6	100	100	100	95-100	65-85	50-65
Urban land.										
22, 23, 24-----										
Hebbronville	0-17	Sandy loam-----	SM	A-2-4	100	100	75-100	13-24	<25	NP-4
	17-58	Fine sandy loam, loam.	SM, SM-SC	A-2-4	100	100	90-100	20-30	<30	NP-7
	58-65	Fine sandy loam, loam.	SM-SC, SC	A-2-4, A-4, A-2-6, A-6	95-100	90-100	90-100	20-40	20-30	4-13
25, 26, 27-----										
Hidalgo	0-17	Fine sandy loam	SC, SM-SC	A-4, A-6	100	95-100	90-100	36-50	20-30	4-11
	17-28	Sandy clay loam, clay loam.	SC, CL	A-6	100	95-100	90-100	36-80	30-40	11-20
	28-80	Clay loam, sandy clay loam.	CL, SC	A-6, A-7-6	90-100	80-100	75-99	44-80	30-44	11-23
28, 29, 30-----										
Hidalgo	0-17	Sandy clay loam	SC, CL	A-6	100	95-100	90-100	36-55	29-40	11-20
	17-28	Sandy clay loam, clay loam.	SC, CL	A-6	100	95-100	90-100	36-80	30-40	11-20
	28-80	Clay loam, sandy clay loam.	CL, SC	A-6, A-7-6	90-100	80-100	75-99	44-80	30-44	11-23
31:*										
Hidalgo-----	0-17	Sandy clay loam	SC, CL	A-6	100	95-100	90-100	36-50	29-40	11-20
	17-28	Sandy clay loam, clay loam.	SC, CL	A-6	100	95-100	90-100	36-80	30-40	11-20
	28-80	Clay loam, sandy clay loam.	CL, SC	A-6, A-7-6	90-100	80-100	75-99	44-80	30-44	11-23
Urban land.										

See footnote at end of table.

Hidalgo County, Texas

159

TABLE 16.--ENGINEERING INDEX PROPERTIES--Continued

Map symbol and soil name	Depth	USDA texture	Classification		Percentage passing sieve number--				Liquid limit Pct	Plas- ticity index
			Unified	AASHTO	4	10	40	200		
	<u>In</u>									
32:* Jimenez-----	0-8	Very gravelly loam.	GC, GM-GC	A-1, A-2-4, A-2-6	30-58	15-40	15-35	15-30	22-35	5-15
	8-10	Cemented-----	---	---	---	---	---	---	---	---
	10-60	Variable-----	---	---	---	---	---	---	---	---
Quemado-----	0-6	Very gravelly sandy loam.	GM, GC, GM-GC	A-1, A-2	30-50	20-50	15-35	15-30	<25	NP-10
	6-12	Very gravelly sandy loam, very gravelly loam, very gravelly sandy clay loam.	GM, GC, GM-GC	A-1, A-2	30-50	20-50	15-35	15-30	18-28	2-10
	12-18	Cemented-----	---	---	---	---	---	---	---	---
	18-60	Variable-----	---	---	---	---	---	---	---	---
33----- Laredo	0-14	Silty clay loam	CL	A-6, A-7-6, A-4	100	100	90-100	85-100	28-44	9-22
	14-65	Silty clay loam, silt loam, very fine sandy loam.	CL	A-6, A-7-6, A-4	100	95-100	90-100	70-95	28-43	9-21
34----- Matamoros	0-65	Silty clay, stratified silt loam to clay.	CH	A-7-6	100	100	100	95-100	51-65	30-41
35, 36, 37----- McAllen	0-14	Fine sandy loam	CL, SC, CL-ML, SM-SC	A-4, A-6	100	100	95-100	36-55	21-30	4-11
	14-72	Sandy clay loam, clay loam, fine sandy loam.	CL, SC	A-6	95-100	90-100	85-100	45-70	28-40	11-20
38----- McAllen	0-14	Sandy clay loam	CL, SC,	A-6	100	100	95-100	36-55	29-40	11-20
	14-72	Sandy clay loam, clay loam, fine sandy loam.	CL, SC	A-6	95-100	90-100	85-100	45-70	28-40	11-20
39, 40, 41----- Mercedes	0-19	Clay-----	CH	A-7-6	85-100	80-100	80-100	75-95	55-76	32-49
	19-57	Clay-----	CH, CL-CH	A-7-6	85-100	80-100	80-100	75-95	50-76	32-49
	57-65	Clay-----	CH, CL	A-7-6	85-100	80-100	80-100	75-95	48-76	32-49
42----- Nueces	0-29	Fine sand-----	SP-SM, SM, SM-SC	A-2-4, A-3	100	95-100	90-100	8-35	<25	NP-6
	29-72	Sandy clay loam, sandy loam.	SC	A-2-6, A-6	90-100	90-100	80-100	20-50	25-40	11-20
43:* Nueces-----	0-29	Fine sand-----	SP-SM, SM, SM-SC	A-2-4, A-3	100	95-100	90-100	8-35	<25	NP-6
	29-72	Sandy clay loam, sandy loam.	SC	A-2-6, A-6	90-100	90-100	80-100	20-50	25-40	11-20
Sarita-----	0-48	Fine sand-----	SM-SC, SP-SM, SM	A-2-4, A-3	100	100	65-100	9-35	<25	NP-7
	48-80	Sandy clay loam, fine sandy loam.	SC	A-2-6, A-6	100	100	80-100	30-50	28-40	11-22
44----- Olmito	0-47	Silty clay-----	CH	A-7-6	100	100	100	90-100	51-70	28-44
	47-65	Silty clay, silty clay loam.	CH	A-7-6	95-100	90-100	85-100	85-100	51-70	28-44

See footnote at end of table.

160

Soil survey

TABLE 16.--ENGINEERING INDEX PROPERTIES--Continued

Map symbol and soil name	Depth	USDA texture	Classification		Percentage passing sieve number--				Liquid limit	Plas- ticity index
			Unified	AASHTO	4	10	40	200		
	<u>In</u>								<u>Pct</u>	
45,* 46,* 47.* Pits										
48, 49----- Racombe	0-13	Sandy clay loam	CL, SC	A-4, A-6	100	100	95-100	45-65	27-35	8-15
	13-49	Sandy clay loam, clay loam.	CL, SC	A-6, A-7	100	95-100	90-100	45-65	34-43	15-22
	49-72	Sandy clay loam, clay loam.	CL, SC	A-6	90-100	80-100	80-95	40-65	30-40	11-20
50----- Ramadero	0-21	Sandy clay loam	CL, SC	A-6, A-4	100	100	95-100	45-65	27-39	9-18
	21-65	Sandy clay loam, clay loam.	CL, SC	A-6, A-7	100	95-100	90-100	45-65	32-42	13-21
51: * Randado-----	0-9	Fine sandy loam	SM, SM-SC	A-2-4	75-100	70-100	70-100	20-35	<25	NP-7
	9-16	Fine sandy loam, sandy clay loam.	SC, SM-SC, GC	A-2-4, A-2-6, A-4, A-6	65-100	60-100	60-100	25-50	25-34	7-14
	16-60	Cemented-----	---	---	---	---	---	---	---	---
Cuevitas-----	0-8	Fine sandy loam	SM, SM-SC, SC	A-2-4	80-100	80-100	80-100	20-35	<28	NP-9
	8-60	Cemented-----	---	---	---	---	---	---	---	---
52, 53----- Raymondville	0-15	Clay loam-----	CL	A-6, A-7-6	100	100	95-100	51-85	37-50	18-30
	15-43	Clay, clay loam	CL, CH	A-6, A-7-6	100	95-100	95-100	75-95	38-55	19-35
	43-65	Clay, clay loam	CL, CH	A-7-6	100	85-100	80-100	75-95	40-53	20-30
54: * Raymondville----	0-15	Clay loam-----	CL	A-6, A-7-6	100	100	95-100	51-85	37-50	18-30
	15-43	Clay, clay loam	CL, CH	A-6, A-7-6	100	95-100	95-100	75-95	38-55	19-35
	43-65	Clay, clay loam	CL, CH	A-7-6	100	85-100	80-100	75-95	40-53	20-30
Urban land.										
55, 56----- Reynosa	0-15	Silty clay loam	CL, CL-ML	A-6, A-4, A-7-6	100	100	95-100	80-100	25-45	7-25
	15-48	Silty clay loam, silt loam.	CL	A-6, A-4, A-7-6	100	100	95-100	80-100	28-44	9-23
	48-65	Stratified silty clay loam to silt loam.	CL, CL-ML	A-6, A-4, A-7-6	100	100	90-100	70-100	20-49	4-29
57: * Reynosa-----	0-15	Silty clay loam	CL, CL-ML	A-6, A-4, A-7-6	100	100	95-100	80-100	25-45	7-25
	15-48	Silty clay loam, silt loam.	CL	A-6, A-4, A-7-6	100	100	95-100	80-100	28-44	9-23
	48-65	Stratified silty clay loam to silt loam.	CL, CL-ML	A-6, A-4, A-7-6	100	100	90-100	70-100	20-49	4-29
Urban land.										
58, 59----- Rio	0-12	Fine sandy loam	SC, SM-SC	A-2-4, A-4	95-100	95-100	95-100	30-48	<30	5-10
	12-38	Clay loam, clay	CL, CH	A-7-6	95-100	95-100	95-100	75-95	43-57	21-32
	38-63	Clay loam, sandy clay, sandy clay loam.	CL	A-7-6	95-100	95-100	85-95	55-80	41-50	20-27

See footnote at end of table.

Hidalgo County, Texas

161

TABLE 16.--ENGINEERING INDEX PROPERTIES--Continued

Map symbol and soil name	Depth In	USDA texture	Classification		Percentage passing sieve number--				Liquid limit Pct	Plas- ticity index
			Unified	AASHTO	4	10	40	200		
60, 61----- Rio	0-12	Clay loam-----	CL	A-6, A-7	95-100	95-100	95-100	70-80	35-45	15-22
	12-38	Clay loam, clay	CL, CH	A-7-6	95-100	95-100	95-100	75-95	43-57	21-32
	38-63	Clay loam, sandy clay, sandy clay loam.	CL	A-7-6	95-100	95-100	85-95	55-80	41-50	20-27
62----- Rio Grande	0-8	Silt loam-----	CL, CL-ML	A-4, A-6	100	100	95-100	70-95	20-30	4-12
	8-65	Stratified silt loam to loamy very fine sand.	CL, CL-ML	A-4, A-6	100	100	95-100	70-100	20-33	4-12
63----- Rio Grande	0-8	Silty clay loam	CL	A-6, A-7	100	100	95-100	80-100	30-43	11-18
	8-65	Stratified silt loam to loamy very fine sand.	CL, CL-ML	A-4, A-6	100	100	95-100	70-100	20-33	4-12
64, 65----- Runn	0-55	Silty clay-----	CH, CL	A-7-6	100	100	95-100	85-98	43-62	21-36
	55-65	Silty clay, silty clay loam, silt loam.	CH, CL, CL-ML	A-6, A-7-6, A-4	100	95-100	90-100	70-98	21-62	4-36
66----- Sarita	0-48	Fine sand-----	SM-SC, SP-SM, SM	A-2-4, A-3	100	100	65-100	9-35	<25	NP-7
	48-80	Sandy clay loam, fine sandy loam.	SC	A-2-6, A-6	100	100	80-100	30-50	28-40	11-22
67----- Tiocano	0-65	Clay-----	CH	A-7-6	100	100	95-100	85-100	56-76	33-49
68.* Urban land										
69.* Ustorthents										
70, 71----- Willacy	0-14	Fine sandy loam	SC, SM-SC	A-2-4, A-4	100	100	95-100	30-45	20-30	5-10
	14-80	Sandy clay loam, fine sandy loam.	SC, CL	A-4, A-6	95-100	90-100	90-100	36-65	28-40	9-20
72.* Willacy----- Urban land.	0-14	Fine sandy loam	SC, SM-SC	A-2-4, A-4	100	100	95-100	30-45	20-30	5-10
	14-80	Sandy clay loam, fine sandy loam.	SC, CL	A-4, A-6	95-100	90-100	90-100	36-65	28-40	9-20
73----- Zalla	0-9	Loamy fine sand	SP-SM, SM, SM-SC	A-2-4	95-100	95-100	70-85	10-25	<25	NP-7
	9-65	Loamy fine sand, fine sand, sand.	SP-SM, SM, SM-SC	A-2-4	95-100	95-100	70-85	10-25	<25	NP-7
74----- Zalla	0-9	Silt loam-----	CL, CL-ML, ML	A-4, A-6	100	100	90-100	70-80	<30	NP-11
	9-65	Loamy fine sand, fine sand, sand.	SP-SM, SM, SM-SC	A-2-4	95-100	95-100	70-85	10-25	<25	NP-7

* See description of the map unit for composition and behavior characteristics of the map unit.

166

Soil survey

TABLE 18.--SOIL AND WATER FEATURES

["Flooding" and "water table" and terms such as "rare," "brief," "apparent," and "perched" are explained in the text. The symbol > means more than. Absence of an entry indicates that the feature is not a concern]

Map symbol and soil name	Hydro-logic group	Flooding			High water table			Cemented pan		Risk of corrosion	
		Frequency	Duration	Months	Depth	Kind	Months	Depth	Hard-ness	Uncoated steel	Concrete
1.* Arents					<u>Ft</u>			<u>In</u>			
2----- Benito	D	Occasional	Long-----	Sep-May	4.0-6.0	Apparent	Sep-May	---	---	High-----	Low.
3, 4----- Brennan	B	None-----	---	---	>6.0	---	---	---	---	Moderate	Low.
5, 6----- Camargo	B	Rare-----	Brief-----	Sep-May	>6.0	---	---	---	---	Moderate	Low.
7----- Cameron	D	None-----	---	---	5.0-6.0	Apparent	Sep-May	---	---	High-----	Low.
8----- Comitas	A	None-----	---	---	>6.0	---	---	---	---	Low-----	Low.
9, 10, 11----- Delfina	B	None-----	---	---	2.5-5.0	Apparent	Sep-May	---	---	High-----	Low.
12----- Delmita	C	None-----	---	---	>6.0	---	---	20-40	Thin	Moderate	Low.
13.* Delmita-----	C	None-----	---	---	>6.0	---	---	20-40	Thin	Moderate	Low.
Randado-----	C	None-----	---	---	>6.0	---	---	8-20	Thin	Moderate	Low.
14----- Falfurrias	A	None-----	---	---	>6.0	---	---	---	---	Low-----	Low.
15**----- Grulla	D	Frequent-----	Very long	Sep-May	+2-6.0	Apparent	Sep-May	---	---	High-----	Low.
16, 17, 18----- Hargill	B	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
19----- Harlingen	D	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
20----- Harlingen	D	None-----	---	---	5.0-6.0	---	---	---	---	High-----	Moderate.
21.* Harlingen-----	D	None to rare	---	---	>6.0	---	---	---	---	High-----	Low.
Urban land.											
22, 23, 24----- Hebbronville	B	None-----	---	---	>6.0	---	---	---	---	Low-----	Low.
25, 26, 27, 28, 29----- Hidalgo	B	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
30----- Hidalgo	B	None-----	---	---	2.5-5.0	Apparent	Sep-May	---	---	High-----	Low.
31.* Hidalgo-----	B	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
Urban land.											
32.* Jimenez-----	C	None-----	---	---	>6.0	---	---	7-20	Thin	High-----	Low.

See footnotes at end of table.

Hidalgo County, Texas

167

TABLE 18.--SOIL AND WATER FEATURES--Continued

Map symbol and soil name	Hydro- logic group	Flooding			High water table			Cemented pan		Risk of corrosion	
		Frequency	Duration	Months	Depth	Kind	Months	Depth	Hard- ness	Uncoated steel	Concrete
					<u>Ft</u>			<u>In</u>			
32:* Quemado-----	C	None-----	---	---	>6.0	---	---	10-20	Thin	Moderate	Low.
33----- Laredo	B	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
34----- Matamoros	C	Occasional	Long-----	Sep-May	>6.0	---	---	---	---	High-----	Low.
35, 36, 37, 38---- McAllen	C	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
39, 40, 41----- Mercedes	D	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
42----- Nueces	C	None-----	---	---	>6.0	---	---	---	---	Moderate	Low.
43:* Nueces-----	C	None-----	---	---	>6.0	---	---	---	---	Moderate	Low.
Sarita-----	A	None-----	---	---	>6.0	---	---	---	---	Low-----	Low.
44, 44----- Olmito	D	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
45,* 46,* 47.* Pits											
48----- Racombes	B	Rare-----	---	---	>6.0	---	---	---	---	High-----	Low.
49----- Racombes	B	Rare-----	---	---	1.5-4.5	Apparent	Sep-May	---	---	High-----	Low.
50----- Ramadero	B	Common-----	Brief-----	Sep-May	>6.0	---	---	---	---	High-----	Low.
51:* Randado-----	C	None-----	---	---	>6.0	---	---	8-20	Thin	Moderate	Low.
Cuevitas-----	D	None-----	---	---	>6.0	---	---	8-14	Thin	Moderate	Low.
52----- Raymondville	D	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
53----- Raymondville	D	None-----	---	---	2.5-4.5	Apparent	Sep-May	---	---	High-----	Low.
54:* Raymondville-----	D	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
Urban land.											
55----- Reynosa	B	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
56----- Reynosa	B	None-----	---	---	1.5-4.5	Apparent	Sep-May	---	---	High-----	Low.
57:* Reynosa-----	B	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
Urban land.											
58**----- Rio	D	Frequent-----	Long-----	Sep-May	+2-6.0	Apparent	Sep-May	---	---	High-----	Low.
59**----- Rio	D	Frequent-----	Long-----	Sep-May	+2-4.5	Apparent	Sep-May	---	---	High-----	Low.

See footnotes at end of table.

168

Soil survey

TABLE 18.--SOIL AND WATER FEATURES--Continued

Map symbol and soil name	Hydro- logic group	Flooding			High water table			Cemented pan		Risk of corrosion	
		Frequency	Duration	Months	Depth	Kind	Months	Depth	Hard- ness	Uncoated steel	Concrete
60**----- Rio	D	Frequent-----	Long-----	Sep-May	<u>Ft</u> +2-6.0	Apparent	Sep-May	<u>In</u> ---	---	High-----	Low.
61**----- Rio	D	Frequent-----	Long-----	Sep-May	+2-4.5	Apparent	Sep-May	---	---	High-----	Low.
62, 63----- Rio Grande	B	Rare-----	Brief-----	Sep-May	>6.0	---	---	---	---	High-----	Low.
64----- Runn	D	None-----	---	---	>6.0	---	---	---	---	High-----	Low.
65----- Runn	D	None-----	---	---	2.5-5.0	Apparent	Sep-May	---	---	High-----	Low.
66----- Sarita	A	None-----	---	---	>6.0	---	---	---	---	Low-----	Low.
67**----- Tlocano	D	Frequent-----	Long-----	Sep-May	+3-6.0	Perched	Sep-May	---	---	High-----	Low.
68.* Urban land											
69.* Ustorthents											
70, 71----- Willacy	B	None-----	---	---	>6.0	---	---	---	---	Moderate	Low.
72:* Willacy----- Urban land.	B	None-----	---	---	>6.0	---	---	---	---	Moderate	Low.
73----- Zalla	A	Occasional	Brief-----	Sep-May	>6.0	---	---	---	---	High-----	Low.
74----- Zalla	A	Rare-----	Brief-----	Sep-May	>6.0	---	---	---	---	High-----	Low.

* See description of the map unit for composition and behavior characteristics of the map unit.
** In the "High water table--Depth" column, a plus sign preceding the range in depth indicates that the water table is above the surface of the soil. The first numeral in the range indicates how high the water rises above the surface. The second numeral indicates the depth below the surface.

Hidalgo County, Texas

153

TABLE 15.--WATER MANAGEMENT

[Some terms that describe restrictive soil features are defined in the Glossary. See text for definitions of "slight," "moderate," and "severe." Absence of an entry indicates that the soil was not evaluated]

Map symbol and soil name	Limitations for--		Features affecting--			
	Pond reservoir areas	Embankments, dikes, and levees	Drainage	Irrigation	Terraces and diversions	Grassed waterways
1.* Arents						
2----- Benito	Moderate: seepage.	Moderate: hard to pack, excess salt.	Percs slowly, excess salt.	Slow intake, percs slowly, excess salt.	Percs slowly---	Excess salt, percs slowly.
3, 4----- Brennan	Moderate: seepage.	Moderate: piping.	Favorable-----	Favorable-----	Favorable-----	Favorable.
5, 6----- Camargo	Moderate: seepage.	Moderate: piping.	Floods-----	Erodes easily	Erodes easily	Erodes easily.
7----- Cameron	Severe: seepage.	Moderate: piping.	Favorable-----	Slow intake---	Favorable-----	Favorable.
8----- Comitas	Severe: seepage.	Moderate: seepage, piping.	Cutbanks cave	Droughty, fast intake.	Too sandy, soil blowing.	Droughty.
9----- Delfina	Moderate: seepage.	Moderate: wetness.	Favorable-----	Wetness, droughty, fast intake.	Soil blowing---	Favorable.
10, 11----- Delfina	Moderate: seepage.	Moderate: wetness.	Favorable-----	Wetness-----	Favorable-----	Favorable.
12----- Delmita	Severe: seepage.	Moderate: thin layer.	Cemented pan---	Soil blowing, cemented pan.	Cemented pan, soil blowing.	Cemented pan.
13:* Delmita-----	Severe: seepage.	Moderate: thin layer.	Cemented pan---	Soil blowing, cemented pan.	Cemented pan, soil blowing.	Cemented pan.
Randado-----	Severe: cemented pan, seepage.	Severe: thin layer.	Cemented pan---	Cemented pan---	Cemented pan---	Cemented pan.
14----- Falfurrias	Severe: seepage.	Severe: seepage, piping.	Cutbanks cave	Droughty, fast intake.	Too sandy-----	Droughty.
15----- Grulla	Slight-----	Severe: hard to pack, ponding.	Ponding, percs slowly, floods.	Ponding, slow intake, percs slowly.	Ponding, percs slowly.	Wetness, percs slowly.
16, 17----- Hargill	Moderate: seepage.	Moderate: piping.	Favorable-----	Favorable-----	Favorable-----	Favorable.
18----- Hargill	Moderate: seepage, slope.	Moderate: piping.	Slope-----	Slope-----	Favorable-----	Favorable.
19----- Harlingen	Slight-----	Severe: hard to pack.	Percs slowly---	Slow intake, percs slowly.	Percs slowly---	Excess salt, percs slowly.
20----- Harlingen	Slight-----	Moderate: hard to pack, excess salt.	Percs slowly, excess salt.	Droughty, slow intake, percs slowly.	Percs slowly---	Excess salt, droughty, percs slowly.
21:* Harlingen-----	Slight-----	Severe: hard to pack.	Percs slowly---	Slow intake, percs slowly.	Percs slowly---	Excess salt, percs slowly.
Urban land.						

See footnote at end of table.

154

Soil survey

TABLE 15.--WATER MANAGEMENT--Continued

Map symbol and soil name	Limitations for--		Features affecting--			
	Pond reservoir areas	Embankments, dikes, and levees	Drainage	Irrigation	Terraces and diversions	Grassed waterways
22, 23, 24----- Hebbronville	Severe: seepage.	Moderate: piping.	Favorable-----	Favorable-----	Soil blowing---	Favorable.
25, 26----- Hidalgo	Moderate: seepage.	Moderate: piping.	Favorable-----	Favorable-----	Favorable-----	Favorable.
27----- Hidalgo	Moderate: seepage, slope.	Moderate: piping.	Slope-----	Slope-----	Favorable-----	Favorable.
28, 29----- Hidalgo	Moderate: seepage.	Moderate: piping.	Favorable-----	Favorable-----	Favorable-----	Favorable.
30----- Hidalgo	Moderate: seepage.	Moderate: piping, wetness, excess salt.	Excess salt---	Wetness, excess salt.	Wetness-----	Excess salt, droughty.
31: * Hidalgo----- Urban land.	Moderate: seepage.	Moderate: piping.	Favorable-----	Favorable-----	Favorable-----	Favorable.
32: * Jimenez-----	Severe: cemented pan.	Severe: thin layer.	Cemented pan---	Droughty, cemented pan, slope.	Large stones, cemented pan.	Large stones, droughty.
Quemado-----	Severe: cemented pan.	Severe: seepage.	Cemented pan---	Droughty, cemented pan, slope.	Large stones, cemented pan.	Large stones, droughty, cemented pan.
33----- Laredo	Severe: seepage.	Moderate: piping.	Favorable-----	Erodes easily	Erodes easily	Erodes easily.
34----- Matamoros	Slight-----	Moderate: hard to pack.	Peres slowly, floods.	Slow intake, peres slowly, floods.	Peres slowly---	Peres slowly.
35, 36, 37, 38---- McAllen	Moderate: seepage.	Moderate: piping.	Favorable-----	Favorable-----	Favorable-----	Favorable.
39----- Mercedes	Slight-----	Severe: hard to pack.	Peres slowly---	Slow intake, peres slowly.	Peres slowly---	Peres slowly.
40----- Mercedes	Slight-----	Severe: hard to pack.	Peres slowly---	Slow intake, peres slowly, excess salt.	Peres slowly---	Excess salt, droughty, peres slowly.
41----- Mercedes	Slight-----	Severe: hard to pack.	Peres slowly---	Slow intake, peres slowly.	Peres slowly---	Peres slowly.
42----- Nueces	Moderate: seepage.	Severe: seepage, piping.	Cutbanks cave	Droughty, fast intake.	Too sandy, soil blowing.	Droughty.
43: * Nueces-----	Moderate: seepage.	Severe: seepage, piping.	Cutbanks cave	Droughty, fast intake.	Too sandy, soil blowing.	Droughty.
Sarita-----	Severe: seepage.	Severe: seepage, seepage.	Cutbanks cave	Droughty, fast intake.	Too sandy-----	Droughty.
44----- Olmito	Slight-----	Moderate: hard to pack.	Peres slowly---	Slow intake, peres slowly.	Peres slowly---	Peres slowly.

See footnote at end of table.

Hidalgo County, Texas

155

TABLE 15.--WATER MANAGEMENT--Continued

Map symbol and soil name	Limitations for--		Features affecting--			
	Pond reservoir areas	Embankments, dikes, and levees	Drainage	Irrigation	Terraces and diversions	Grassed waterways
45,* 46,* 47.* Pits						
48----- Racombes	Moderate: seepage.	Slight-----	Favorable-----	Favorable-----	Favorable-----	Favorable.
49----- Racombes	Moderate: seepage.	Severe: wetness, excess salt.	Excess salt----	Wetness, droughty, excess salt.	Wetness-----	Excess salt, droughty.
50----- Ramadero	Moderate: seepage.	Moderate: piping.	Floods-----	Floods-----	Favorable-----	Favorable.
51:* Randado-----	Severe: cemented pan, seepage.	Severe: thin layer.	Cemented pan---	Cemented pan---	Cemented pan---	Cemented pan.
Cuevitas-----	Severe: cemented pan, seepage.	Severe: thin layer.	Cemented pan---	Cemented pan---	Cemented pan---	Cemented pan.
52----- Raymondville	Slight-----	Moderate: hard to pack.	Peres slowly---	Slow intake, peres slowly.	Peres slowly---	Peres slowly.
53----- Raymondville	Slight-----	Severe: excess salt.	Peres slowly, excess salt.	Wetness, droughty, excess salt.	Wetness, peres slowly.	Excess salt, droughty, peres slowly.
54:* Raymondville-----	Slight-----	Moderate: hard to pack.	Peres slowly---	Slow intake, peres slowly.	Peres slowly---	Peres slowly.
Urban land.						
55----- Reynosa	Severe: seepage.	Moderate: thin layer, piping.	Favorable-----	Erodes easily	Erodes easily	Erodes easily.
56----- Reynosa	Severe: seepage.	Moderate: piping, wetness, excess salt.	Excess salt----	Wetness, excess salt, erodes easily.	Erodes easily, wetness.	Excess salt, erodes easily, droughty.
57:* Reynosa-----	Severe: seepage.	Moderate: thin layer, piping.	Favorable-----	Erodes easily	Erodes easily	Erodes easily.
Urban land.						
58----- Rio	Slight-----	Severe: ponding.	Ponding, peres slowly, floods.	Ponding, peres slowly, floods.	Ponding, peres slowly.	Wetness, peres slowly.
59----- Rio	Slight-----	Severe: ponding, excess salt.	Ponding, peres slowly, floods.	Ponding, droughty, peres slowly.	Ponding, peres slowly.	Wetness, excess salt, droughty.
60----- Rio	Slight-----	Severe: ponding.	Ponding, peres slowly, floods.	Ponding, peres slowly, floods.	Ponding, peres slowly.	Wetness, peres slowly.
61----- Rio	Slight-----	Severe: ponding, excess salt.	Ponding, peres slowly, floods.	Ponding, droughty, peres slowly.	Ponding, peres slowly.	Wetness, excess salt, droughty.
62, 63----- Rio Grande	Severe: seepage.	Severe: piping.	Floods-----	Erodes easily, floods.	Erodes easily	Erodes easily.

See footnote at end of table.

156

Soil survey

TABLE 15.--WATER MANAGEMENT--Continued

Map symbol and soil name	Limitations for--		Features affecting--			
	Pond reservoir areas	Embankments, dikes, and levees	Drainage	Irrigation	Terraces and diversions	Grassed waterways
64----- Runn	Moderate: seepage.	Moderate: hard to pack.	Percs slowly---	Slow intake, percs slowly, excess salt.	Percs slowly---	Percs slowly.
65----- Runn	Moderate: seepage.	Moderate: hard to pack, wetness, excess salt.	Percs slowly, excess salt.	Slow intake, percs slowly, excess salt.	Wetness, percs slowly.	Excess salt, erodes easily, percs slowly.
66----- Sarita	Severe: seepage.	Severe: seepage, seepage.	Cutbanks cave	Droughty, fast intake.	Too sandy-----	Droughty.
67----- Tiocano	Slight-----	Severe: hard to pack, ponding.	Ponding, percs slowly, floods.	Ponding, slow intake, percs slowly.	Ponding, percs slowly.	Wetness, percs slowly.
68.* Urban land						
69.* Ustorthents						
70, 71----- Willacy	Moderate: seepage.	Slight-----	Favorable-----	Favorable-----	Favorable-----	Favorable.
72.* Willacy----- Urban land.	Moderate: seepage.	Slight-----	Favorable-----	Favorable-----	Favorable-----	Favorable.
73, 74----- Zalla	Severe: seepage.	Severe: seepage, piping.	Floods-----	Droughty, fast intake.	Too sandy-----	Droughty.

* See description of the map unit for composition and behavior characteristics of the map unit.



**Planning & Zoning Commission
Standardized Agenda Request Form**

Date of Meeting: February 3, 2021	Agenda Item No. (to be assigned by PCE): V. B.
From: Rebekah de la Fuente, Planning Director, on behalf of Ruben Alfaro.	
Subject/Agenda Item: Discussion and consideration for the Preliminary Plat for Gonzalez-Vasquez Subdivision– being 2.24 acres out of Lot 1, Kevin Subdivision, Weslaco, Hidalgo County, Texas located approximately 733 FT west of Westgate drive on mile 10. Possible Action.	
Discussion/Overview: The proposed two (2) lot subdivision is outside the City of Weslaco. This subdivision is being serviced with water by the North Alamo Water Supply Company through an 8” waterline and sewer by OSSF. The property is within a Flood Zone “X”. Applicant is requesting a variance for OSSF.	
If item requires Publication Notice, provide date and periodical of publication; indicate if comments received from letters mailed to property owners: N/A	
Staff recommendation for Commission’s Action: Staff recommends approval of Preliminary Plat and compliance with the ordinance on the variance.	
Additional Action Prompted: [X] Mayor’s Signature [] Public Hearing [] Budget Amendment [] Resolution [] Ordinance – First Reading [] Ordinance – Final Reading	
Advisory Review, (if any): (name of board/committee, date of action, recommendation): N/A	
If item previously considered, provide date and action by Commission: N/A	
Attachments,(if any): Application for Subdivision platting, Staff’s comments, Drainage Report, Subdivision plat and Utility layout.	
Responsibilities upon Commission’s Action: Planning staff will advise applicant.	



SUBDIVISION PLATTING APPLICATION

The Planning & Zoning Commission meets every 1st Wednesday of each month at 5:30 pm.

The City Commission meets every 1st and 3rd Tuesday of each month at 5:30 pm

FILE NO. _____

This form shall be completed by the Property Owner or Applicant and submitted to the Planning Department along with the required number of copies of the respective plat, review fee and all other required information listed below and in the Subdivision Ordinance. The submittal of an application does not constitute acceptance for processing until the staff reviews and determines the application is complete.

STAFF USE ONLY

☐ Single Lot Variance ☐ Minor Plat ☐ Planned Unit Development ☐ Standard Subdivision

GENERAL INFORMATION

Name of Subdivision: Gonzalez-Vasquez Subdivision

Location: _____

Legal Description: _____

Is subdivision inside city limits? ☐ YES ☒ NO

If subdivision is in the ETJ, indicate? ☐ 3.5 Mile ☐ 5 Mile

If no submit letter of Annexation (Contiguous or Consensual)

Existing Zoning: Residential

Existing Land Use: Residential Proposed Land Use: Residential

Number of Lots Proposed: 2 Gross Acreage: 2.74

Title Report Submitted: ☐ YES ☐ NO

OWNER INFORMATION

Owner's Name: Roberto Gonzalez Telephone: 956 280 7347

Address: RT 6 Box 279 E Fax: _____

City: Weslaco State: TX Zip: 78596 E-mail: _____

ENGINEER INFORMATION

Name: Ruben Alfaro Telephone: 956 207 6072

Address: 7800 N. Ft St. Fax: _____

City: McAllen State: TX Zip: 78504 E-mail: ruben.alfaro@achc-engineering.com

UTILITY PROVISIONS

Will proposed subdivision connect to:

☒ YES ☐ NO Water Provision: NAWSC

☐ YES ☒ NO Wastewater Provision: Septic Tank

☒ YES ☐ NO Electric Company: _____

☒ YES ☐ NO Phone Utility _____	☐ YES ☒ NO Gas Utility	☒ YES ☐ NO Cable Utility
---	---	---

Proposed subdivision is in the following districts:

☒ YES ☐ NO Drainage District <u>HCCDD No. 1</u>	☒ YES ☐ NO Irrigation District <u>HCCID No. 9</u>
--	--

Has the property been assessed as flat rate irrigable property: ☐ YES ☒ NO

Have Water Rights been conveyed to City/Water Supplier? ☒ YES ☐ NO

(Attach written proof of such assessment or that it has never been assessed as such a property) If YES, attach an estimate from the irrigation district of the proportional water rights for the subdivision as calculated under Texas Water Code § 49.505.

SUBMITTALS REQUIRED FOR MINOR PLAT REVIEW

Two (2) sets of plats **folded and stapled** (24 x 36) and forward a copy in PDF format to mhinojosa@weslacotx.gov & rdelafuente@weslacotx.gov

\$355.00 Planning Review fee

One 11" X 17" reduced copy of plat

Plat Layout

Existing & Proposed Easements

Existing & Proposed ROW

Existing & Proposed Drainage Easements

Contours

Flood Zones

Adjoiners

Existing street names

Drainage plans and calculations with engineer's seal

Elevations

Flood directional arrows

Detention areas

Street names

Proof of ownership of the property

If septic tank system required, submit soil evaluation report

Water Rights associated with the property

Tax Receipt for all taxing entities showing that taxes are paid in full

SUBMITTALS REQUIRED FOR PRELIMINARY (P & Z)

☒ Twelve (12) sets of preliminary plat **folded and stapled** (24 x 36) and forward a copy in PDF format to mhinojosa@weslacotx.gov & rdelafuente@weslacotx.gov

\$350.00 (one time fee for preliminary and final plat)

One 11" X 17" reduced copy of plat

Plat Layout

Existing & Proposed Easements

Existing & Proposed ROW

Existing & Proposed Drainage Easements

255 S. KANSAS AVE ■ WESLACO, TEXAS 78596-6285 ■ 956-447-3401 ■ (Fax) 956-973-3128 ■ WWW.WESLACOTX.GOV

- _____Contours
- _____Flood Zones
- _____Adjoiners
- _____Existing & Proposed street names
- _____Utility Layout
- _____Existing & Proposed Utilities
- _____Proposed Fire Hydrants
- _____Adjoiners
- _____Street names
- _____Drainage plans and calculations with engineer's seal
- _____Elevations
- _____Flood directional arrows
- _____Detention areas
- _____Street names
- _____Proof of ownership of the property
- _____If septic tank system required, submit soil evaluation report
- _____Water Rights associated with the property
- _____Tax Receipt for all taxing entities showing that taxes are paid in full
- _____Number of fire hydrants proposed for subdivision
- _____Trip Generation Worksheet

SUBMITTALS REQUIRED FOR FINAL (P & Z) **Will not apply to Single Lot Variance**

- _____Twelve (12) sets of plans **FOLDED & STAPLED** (24 x 36) & PDF copy **with all corrections**
- _____Plats to be sealed by Professional Engineer
- _____Approved Drainage Report
- _____Traffic Impact Analysis (If required)

SUBMITTALS REQUIRED FOR FINAL (City Commission)

- _____One set of 8 ½ x 11 of plat and utilities with all corrections done

SUBMITTALS REQUIRED FOR PRE-CONSTRUCTION MEETING

- _____Seven (7) full sets of construction plans 24 x 36 and one (1) 11 x 17 with plan & profile.
- _____Engineering cost estimates for 3% geotechnical testing fees and 2% inspection fees
- _____Notice of Intent
- _____SW3P

SUBMITTALS REQUIRED FOR RECORDING OR HIDALGO COUNTY PLANNING

- _____Electronic file of final plat and as-builds
- _____Reproducible plat to be recorded with all required signatures
- _____3% geotechnical testing fees or negotiated Material Testing fee by City, whichever is higher
- _____2% inspection fee
- _____Park Fees
- _____Checks or Receipts: HCCID #9; HCDD #1; County Clerk
- _____Tax certificates
- _____Memo from engineering inspector releasing subdivision
- _____Water Rights associated with the property dedicated and assigned to City of Weslaco or payment of fees sufficient to meet the needs necessitated and attributable to development
- _____30 Year Water and 30 Year Sewer Service Agreements
- _____Park dedication/Fees in lieu of

SUBMITTALS REQUIRED FOR RECORDING BY SECURITY

- _____Sealed engineering cost estimates
- _____Letter of Credit/Performance Bond/Escrow

** Any revisions requested would require resubmission of plats and reduced copy reflecting changes.

AUTHORIZATION AND ACKNOWLEDGEMENTS

I certify that I am the actual owner of the property described above and this application is being submitted with my consent (include corporate name if applicable); and the following person listed below is my authorized agent to act on my behalf.

I certify that the above information is correct and complete to the best of my knowledge. I understand that I must comply with all applicable local, state, and federal regulations.

Owner Printed Name: Roberto Gonzalez

Owner Signature: [Signature] Date: 01-26-21

Ruben Alfaro is the authorized agent

Authorized Agent Signature: [Signature] Date: 01-26-21

Authorized Agent Printed Name: Ruben Alfaro

THIS PAGE FOR STAFF USE ONLY

Date Received: _____ Received By: _____ Date Paid: _____

P & Z Commission Approval on Preliminary Plat: _____

P & Z Commission Approval on Final Plat: _____

City Commission Approval on Final Plat: _____

Preconstruction Meeting Date: _____

Date Recorded: _____

General Comments: _____

CITY OF WESLACO
956-968-3181

REC#: 02714981 1/27/2021 9:40 AM
OPER: KAREV TERM: 041
REF#: 121
PAID BY:

TRAN: 203.0000 SUBDIVISION INSPECT
gonzalez-vasquez subdivision
101-400-1025
SUBDIVISION INSPECT 355.00CR

TRAN: 115.0000 FIRE MARSHAL INSPECT
PLAN REVIEW
101-400-3110
FIRE MARSHALL INSPE 75.00CR

TENDERED: 75.00 CHECK
355.00 CHECK
APPLIED: 430.00-

CHANGE: 0.00

255 S. KANSAS AVE ■ WESLACO,

WWW.WESLACOTX.GOV



SUBDIVISION REVIEW APPLICATION

The Planning & Zoning Commission meets every 1st Wednesday of each month at 5:30 pm.

The City Commission meets every 1st and 3rd Tuesday of each month at 5:30 pm

FILE NO. _____

This form shall be completed by the Property Owner or Applicant and submitted to the Planning Department along with the required number of copies of the respective plat, review fee and all other required information listed below and in the Subdivision Ordinance. The submittal of an application does not constitute acceptance for processing until the staff reviews and determines the application is complete.

GENERAL INFORMATION

Name of Subdivision: GONZALEZ-VASQUEZ SUBDIVISION

Location: 1928 W. MILE 10 N WESLACO, TX 78596

Legal Description: A 2.24-ACRE TRACT OF LAND INCLUDING ALL OF LOT 1 OF KEVIN SUBDIVISION AS RECORDED IN VOLUME 38 PAGE 38 OF HIDALGO COUNTY MAP RECORDS.

Is subdivision inside city limits? ☐ YES ☒ NO

If subdivision is in the ETJ, indicate? ☒ 3.5 Mile ☐ 5 Mile

If no submit letter of Annexation (Contiguous or Consensual)

Existing Zoning: RESIDENTIAL

Existing Land Use: RESIDENTIAL Proposed Land Use: RESIDENTIAL

Number of Lots Proposed: 2 Gross Acreage: 2.24

Title Report Submitted: ☐ YES ☒ NO

OWNER INFORMATION

Owner's Name: ROBERTO GONZALEZ Telephone: (956) 280-7347

Address: 1928 W. MILE 10 N

Fax: _____

City: WESLACO State: TX Zip: 78596 E-mail: _____

ENGINEER INFORMATION

Name: RUBEN ALFARO Telephone: (956) 207-6072

Address: 7800 N. 1ST ST.

Fax: _____

City: MCALLEN State: TX Zip: 78504 E-mail: ruben.alfaro@achc-engineering.com

255 S. KANSAS AVE ■ WESLACO, TEXAS 78596-6285 ■ 956-447-3401 ■ (Fax) 956-973-3128 ■

UTILITY PROVISIONS

Will proposed subdivision connect to:

- ☒ YES ☐ NO Water Provision: North Alamo Water Supply Corporation
- ☐ YES ☒ NO Wastewater Provision: Septic Tank to be used
- ☒ YES ☐ NO Electric Company: MVEC/AEP

☐ YES ☐ NO Phone Utility	☐ YES ☐ NO Gas Utility	☐ YES ☐ NO Cable Utility
--	--	--

Proposed subdivision is in the following districts:

☒ YES ☐ NO Drainage District <u>HCDD No. 1</u>	☒ YES ☐ NO Irrigation District <u>HCCID No. 9</u>
---	--

Has the property been assessed as flat rate irrigable property: ☐ YES ☐ NO

Have Water Rights been conveyed to City/Water Supplier? ☐ YES ☐ NO

(Attach written proof of such assessment or that it has never been assessed as such a property) If YES, attach an estimate from the irrigation district of the proportional water rights for the subdivision as calculated under Texas Water Code § 49.505.

SUBMITTALS REQUIRED FOR SUBDIVISION REVIEW


- _____ Seven (7) sets of preliminary plat folded and stapled (24 x 36) and forward a copy in PDF format to _____ & _____
- _____ \$55.00 Subdivision Review fee
- _____ One 11" X 17" reduced copy of plat
- _____ Plat Layout
- _____ Existing & Proposed Easements
- _____ Existing & Proposed ROW
- _____ Existing & Proposed Drainage Easements
- _____ Contours
- _____ Flood Zones
- _____ Adjoiners
- _____ Existing & Proposed street names
- _____ Utility Layout
- _____ Existing & Proposed Utilities
- _____ Proposed Fire Hydrants
- _____ Adjoiners
- _____ Street names
- _____ Drainage plans and calculations with engineer's seal
- _____ Elevations
- _____ Flood directional arrows
- _____ Detention areas
- _____ Street names
- _____ Proof of ownership of the property
- _____ If septic tank system required, submit soil evaluation report
- _____ Water Rights associated with the property
- _____ Tax Receipt for all taxing entities showing that taxes are paid in full
- _____ Number of fire hydrants proposed for subdivision
- _____ Trip Generation Worksheet

AUTHORIZATION AND ACKNOWLEDGEMENTS


I certify that I am the actual owner of the property described above and this application is being submitted with my consent (include corporate name if applicable); and the following person listed below is my authorized agent to act on my behalf.

I certify that the above information is correct and complete to the best of my knowledge. I understand that I must comply with all applicable local, state, and federal regulations.

Owner Printed Name: ROBERTO GONZALEZ

Owner Signature:  Date: 10/27/20

RUBEN ALFARO is the authorized agent

Authorized Agent Signature:  Date: 10/27/20

Authorized Agent Printed Name: RUBEN ALFARO

THIS PAGE FOR STAFF USE ONLY

Date Received: _____ Received By: _____ Date Paid: _____

Preliminary Subdivision Review Date: _____

General Comments: _____

1305803

General Warranty Deed

Date: January 2, 2003

Grantor: Francisco J. Jaramillo, Jr. and wife, Maria De La Luz Jaramillo

Grantor's Mailing Address:

1002 E. Jefferson
Harlingen, Texas 78550
Cameron County

Grantee: Robert Gonzalez and wife, Mary Ellen Gonzalez

Grantee's Mailing Address:

Rt. 6 Box 279 E
Weslaco, Texas 78596

Consideration:

TEN AND NO/100 DOLLARS (\$10.00) and other good and valuable consideration.

Property (including any improvements):

Lot One (1), Kevin Subdivision, an addition to the City of Weslaco, Hidalgo County, Texas, as per map or plat thereof recorded in Volume 38, Page 38, Map Records, Hidalgo County, Texas.



Reservations from and Exceptions to Conveyance and Warranty:

Liens described as part of the Consideration and any other liens described in this deed as being either assumed or subject to which title is taken; validly existing easements, rights-of-way, and prescriptive rights, whether of record or not; all presently recorded and validly existing instruments, other than conveyances of the surface fee estate, that affect the Property; and taxes for 2002, which Grantee assumes and agrees to pay, and subsequent assessments for that and prior years due to change in land usage, ownership, or both, the payment of which Grantee assumes.

Grantor, for the Consideration and subject to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty, grants, sells, and conveys to Grantee the Property, together with all and singular the rights and appurtenances thereto in any way belonging, to have and to hold it to Grantee and Grantee's heirs, successors, and assigns forever. Grantor binds Grantor and Grantor's heirs and successors to warrant and forever defend all and singular the Property to Grantee and Grantee's heirs, successors, and assigns against every person whomsoever lawfully claiming or to claim the same or any part thereof, except as to the

Reservations from Conveyance and the Exceptions to Conveyance and Warranty.


When the context requires, singular nouns and pronouns include the plural.


Francisco J. Jaramillo, Jr.

Maria De La Luz Jaramillo

STATE OF TEXAS)

COUNTY OF CAMERON)

This instrument was acknowledged before me on ^{(29) Sept.} January 26, 2003, by Francisco J. Jaramillo, Jr. and wife, Maria De La Luz Jaramillo.




Notary Public, State of Texas

GM:mb\02-27,304

PREPARED IN THE OFFICE OF:
McCullough and McCullough
P.O. Box 2244
Harlingen, Texas 78551
AFTER RECORDING RETURN TO:
Same

Filed for Record in:
Hidalgo County
by J. D. Salinas, III
County Clerk
On: Mar 05, 2004 at 02:30P
As a Recording
Document Number: 1305803
Total Fees: 16.00
Receipt Number - 567248
By,
Gilbert Salinas, Deputy

Rebekah M. De La Fuente

From: Rebekah M. De La Fuente
Sent: Thursday, November 12, 2020 11:12 AM
To: 'Ruben Alfaro'
Subject: RE: Gonzalez-Vasquez Subdivision

Good Morning

Below are the comments for each department. Once revised email over a pdf copy of the plat sheets for re-review. After you have been cleared by all departments you will be authorized to proceed with the subdivision platting application.

Fire Marshal Comments:

This subdivision is approved by our office. Please add the \$75.00 fire plan review fee.

Planning Comments:

- Add Plat Note: Storm detention must be calculated at a proposed 50-year storm event or ____ acres feet.
- Add Plat Note: Identify benchmark and on plat
- Add Plat Note: Streetlight must be located every 300 feet
- Include all appropriate signature lines.- Missing Hidalgo County Recording
- Update Plat Note 4: No permanent structures are permitted over any easements. Easements shall be kept clear of buildings, sheds, shrubs, trees and other plantings (except low, less an 18" mature heights, ground cover, grass or flowers) and other obstructions that would interfere with the operations and maintenance of the easement
- Minimum Building Setback lines shall be as follows:
Front: 25 ft.
Rear: 25 ft.
Side: 5ft
A variance request will be required for proposed setbacks
- Update Plat Note 9: A 4ft. sidewalk is required along all interior streets upon the issuance of a building permit .
- Add Plat Note: No more than one single family detached dwelling shall be located on each lot. Applications for construction are required prior to occupying the lot.

Engineering Comments:

General

- Require a Signed and Sealed Drainage Report

Plat Sheet

- Remove words like "Apparent" from easement and ROW information.
- Need Dimensions from the Centerline of Mile 10 North Road to the proposed subdivision.
- Remove References to Hidalgo County Irrigation District No. 2.
- Populate lot line information of adjacent property owners North East of the Subdivision.
- Replace "Swale Easement" with "Drainage Easement".
- Callout the existing Centerline of Mile 10 N Road and change linetype to a centerline.
- Provide Drainage Volume Quantities in General Notes.
- To remove EOP Pavement and Pavement Dimensions

Utility Sheet

- Callout Existing NAWSC Waterline and Size.
- Update Legend to include Pavement/Hatches, Structures, Fencelines, etc.
- Access Easement and NAWSC Easement extend towards the back of Lot 2, is this correct? Why is this not shown on the Plat.
- Provide Drainage Swale Cross Section and show extents on layout and where it is tying into.
- Provide Drainage Report Volume Calculations.
- Callout Existing Structure to the East of the Subdivision.
- Show Tops and Flows of existing drainage structures

Public Works Comments:

no comments water and sewer outside the city north alamo water\

Rebekah de la Fuente, CFM
Planning & Code Enforcement Director

City of Weslaco
255 S. Kansas Avenue
Weslaco, TX 78596
Ph: (956) 447-3401
Fax: (956) 973-3128
rdelafuente@weslacotx.gov



From: Ruben Alfaro <ruben.alfaro@achc-engineering.com>
Sent: Wednesday, November 4, 2020 12:09 PM
To: Rebekah M. De La Fuente <rdelafuente@weslacotx.gov>
Subject: Re: Gonzalez-Vasquez Subdivision

Rebekah,

Please see attached PDF's. as per the drainage report, do we have to submit a new one? property already has a required detention in the existing plat and we are only dividing the lot in 2.
in case we need it I will prepare that and get it to you ASAP. let me know.

Best,

Ruben Alfaro

On Mon, Nov 2, 2020 at 9:46 AM Rebekah M. De La Fuente <rdelafuente@weslacotx.gov> wrote:

Good Morning,

We are in receipt of your submittal for the above referenced Subdivision. Please submit PDF copies of the plat sheets you submitted and a copy of the Drainage Report. So that I may begin to route it out for staff review.

Thank you

Rebekah M. De La Fuente

From: Rebekah M. De La Fuente
Sent: Friday, January 22, 2021 1:52 PM
To: Ruben Alfaro
Subject: RE: Gonzalez-Vasquez Subdivision

Good afternoon:

Your subdivision has been cleared with comments to proceed with the Subdivision Platting Application. Please submit your Application, \$355.00 application fee, the \$75.00 Fire Review Fee, 12 sets of plats, utility and drainage sheet and the most up to date drainage report.

Engineering Comments: Approved

With the contingency that they provide us a copy of the approved drainage report from Drainage District.

Thank you,

Rebekah de la Fuente, CFM
Planning & Code Enforcement Director

City of Weslaco
255 S. Kansas Avenue
Weslaco, TX 78596
Ph: (956) 447-3401
Fax: (956) 973-3128
rdelafuente@weslacotx.gov



**Proposed
Gonzalez-Vasquez Subdivision
Hidalgo County, Texas**


DRAINAGE REPORT

Prepared For:

**Hidalgo County Drainage District
902 N. Doolittle
Edinburg, Texas, 78541**

Prepared By:

Ruben Alfaro, P.E.



Reg. Engineering No. F-21299

**7800 N. 1st Street
McAllen, Texas 78504
(956) 207-6072**

January 2021




TABLE OF CONTENTS

DRAINAGE REPORT

ATTACHMENTS

LOCATION MAP

SUBDIVISION PLAT

SITE PLAN

FLOOD INSURANCE RATE MAP

DRAINAGE CALCULATIONS

RUNOFF CALCULATIONS

DETENTION STORAGE CALCULATIONS

SOIL PROPERTIES

SOIL MAP

MAP UNIT DESCRIPTION

PHYSICAL SOIL PROPERTIES

ENGINEERING PROPERTIES

DRAINAGE REPORT
Gonzalez-Vasquez Subdivision
Hidalgo County, Texas

Introduction:

The proposed Gonzalez-Vasquez Subdivision (intended for residential use) is a 2.24 acre two lot subdivision out of lot 1 of Kevin Subdivision in Hidalgo County, Texas. This report is intended to fulfill the drainage requirements of Gonzalez-Vasquez Subdivision. Please see the attached Plat for more details.

This property is located along Mile 10 north between mile 6 and mile 6 and a half roads, IN Hidalgo County within the ETJ limits of Weslaco, Texas. Currently, there is a single family home located on the site. Residential developments are adjacent to the subdivision to the East, West and North and a vacant/agricultural lot to the South. Please see the attached Location Map and Plat for reference.

FEMA:

According to the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Maps, the subdivision is located in "*Zone B*" *Community Panel Number 480349 0005 B* Map Effective *March 4, 1980*. "*Zone B*" are areas between limits of the 100-year flood and 500year flood or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile. Please see the attached FEMA Maps for reference. The QUAD Maps has also been included in Attachments.

Soil:

According to the Soil Survey Report prepared for this Subdivision in Hidalgo County by the U.S.D.A. Soil Conservation Services, the site consists of two soil types; about 40% is composed of (25)-Hidalgo fine sandy loam, with 0 to 1 percent slopes and about 60% is composed of (48)-Hidalgo sandy clay loam with 0 to 1 percent slopes. Both Soil types belong to soil group B; ***Soil Group B*** defined as soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.


Existing Drainage Conditions:

Existing storm runoff within this property currently flows overland in a southeasterly direction. Runoff is currently retained in the existing green areas along the residential property and no additional volume is outfalling to existing Mile 10 N. road.

Drainage Requirements:


The pre-developed peak runoff from a 10-year storm determined using the rational method is 2.30 cfs and the anticipated peak runoff after development is calculated to be 3.53 cfs for a 50-year return frequency.


In accordance with the County's drainage requirements of not increasing the amount of existing runoff, we have calculated that 3,079 cubic feet of storm runoff to be retained within the property through seepage into the existing green areas.




A handwritten signature in black ink, appearing to read "Ruben Alfaro", written over a horizontal line.

Ruben Alfaro, P.E.
ACHC Engineering F#-21299







ACHC ENGINEERING

FIRM REGISTRATION NO. F-21299
7800 N. 1ST ST.
McALLEN, TEXAS 78504
PHONE (956) 207-6072

EXHIBIT A

Drainage Calculations, Area 1

Project Name: Gonzalez-Vasquez Subdivision Hidalgo County, TX

Project No.: 017-2020

I. General Information

1. Governing Equation: $Q = CIA$ (Ratnl. Method), TxDOT IDF Curves for **Hidalgo County** & Mannings Equation (normal depth calculations)

2. TxDOT Intensity Constants for $I = b/(Tc+d)^e$ Velocity Constants

Undeveloped	Developed	Slope =	%	proposed	Length =	ft	Drop =	in
10 year storm	50 year storm	0.15	0.15	existing	670	670	12	12
b= 87	b= 99	k = 0.213	k = 0.213	grassed waterway				
e= 0.778	e= 0.749	k = 0.213	k = 0.213	grassed waterway				
d= 9.2	d= 9.2	Ku = 3.28						

where Tc, is calculated with an average overland flow velocity (0-10% slopes):

$$V = (Ku)(k)(Sp)^{1/2}$$

- a) existing unimproved conditions: vel = 0.27 ft/sec
b) proposed residential conditions: vel = 0.27 ft/sec

3) Accepted Runoff Coefficients

a) Building/Roofs	c = 0.90		
b) Asphalt	c = 0.90		
c) Detention/Trench Trough	c = 0.20		
d) Concrete	c = 0.90		
e) Unimproved area (grass)	c = 0.20		
4) Total Area =	2.240 ac	0.30	Cumulative Areas
Area 1	0.114 ac	0.90	Building/Roofs
Area 2	0.207 ac	0.90	Asphalt
Area 3	1.919 ac	0.20	Unimproved area (grass)

II. Existing Conditions

A) Drainage area					
Length of runoff =	670 ft				
Tc =	670 / (V ft/sec x 60 sec) =	41.4 min.	Use	10.0 min	If Tc < than 10
I (10 yr) = b/(Tc+d)^e =	4.11 in/hr				
Q=CIA=	0.25 4.11 2.24 =	2.30 cfs			

III. Ultimate Developed Conditions

Weighted Runoff Coefficient					
C= (C1A1+C2A2+C3A3+C4A4+...)/Atotal=	0.30				
A) Drainage area					
Length of runoff =	670 ft				
Drainage area =	2.24 ac.				
Tc =	670 / (V ft/sec x 60 sec) =	41.4 min.	Use	10.0 min	If Tc < than 10
I (50 yr) = b/(Tc+d)^e =	5.24 in/hr				
Q=CIA=	0.30 5.24 2.24 =	3.53 cfs			

IV. Comments

Qdev = 3.53 cfs
Qexist = 2.30 cfs
Difference = 1.22 cfs

ACHC ENGINEERING

FIRM REGISTRATION NO. F-21299

7800 N. 1ST ST.

McALLEN, TEXAS 78504

PHONE (956) 207-6072

Exhibit B Detention Storage Requirements

PROJECT NAME: GONZALEZ-VASQUEZ SUBDIVISION
HIDALGO COUNTY, TEXAS

Prop. Runoff C = 0.3 Exist Runoff C = 0.25
Area = 2.24 Exist. Intensity = 4.11
Post Dev. Tc = 41.4 min

Time (minutes)	I 50 yrs (in./hr.)	Q (c.f.s.)	Vol. (c.f.)	Qexist. (c.f.s.)	Vol. exist. (c.f.)	Vol. stored (c.f.)
5	13.57	9.12	2,736	2.30	3,204	(468)
10	10.83	7.27	4,365	2.30	3,549	816
15	9.10	6.12	5,505	2.30	3,894	1,611
20	7.91	5.31	6,377	2.30	4,240	2,137
25	7.03	4.72	7,081	2.30	4,585	2,496
30	6.34	4.26	7,672	2.30	4,930	2,742
35	5.80	3.90	8,181	2.30	5,275	2,906
40	5.35	3.60	8,628	2.30	5,621	3,008
45	4.98	3.34	9,028	2.30	5,966	3,062
50	4.66	3.13	9,390	2.30	6,311	3,079
55	4.38	2.95	9,720	2.30	6,656	3,064
60	4.14	2.78	10,025	2.30	7,001	3,023
65	3.93	2.64	10,307	2.30	7,347	2,960
70	3.75	2.52	10,571	2.30	7,692	2,879
75	3.58	2.40	10,818	2.30	8,037	2,781
80	3.43	2.30	11,052	2.30	8,382	2,669
85	3.29	2.21	11,272	2.30	8,728	2,545
90	3.16	2.13	11,482	2.30	9,073	2,409
95	3.05	2.05	11,681	2.30	9,418	2,263
100	2.94	1.98	11,872	2.30	9,763	2,109
105	2.85	1.91	12,055	2.30	10,109	1,946
110	2.76	1.85	12,230	2.30	10,454	1,776
115	2.67	1.80	12,398	2.30	10,799	1,599
120	2.60	1.74	12,560	2.30	11,144	1,416



A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for Hidalgo County, Texas

Gonzalez-Vasquez Subdivision



December 1, 2020

Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require


alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
Soil Map	5
Soil Map.....	6
Legend.....	7
Map Unit Legend.....	8
Map Unit Descriptions.....	8
Hidalgo County, Texas.....	10
25—Hidalgo fine sandy loam, 0 to 1 percent slopes.....	10
28—Hidalgo sandy clay loam, 0 to 1 percent slopes.....	11
48—Racombes sandy clay loam, 0 to 1 percent slopes.....	13
References	15

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



Custom Soil Resource Report

MAP LEGEND

	Area of Interest (AOI)		Spoil Area
	Area of Interest (AOI)		Stony Spot
	Soils		Very Stony Spot
	Soil Map Unit Polygons		Wet Spot
	Soil Map Unit Lines		Other
	Soil Map Unit Points		Special Line Features
	Special Point Features		Water Features
	Blowout		Streams and Canals
	Borrow Pit		Transportation
	Clay Spot		Ralls
	Closed Depression		Interstate Highways
	Gravel Pit		US Routes
	Gravelly Spot		Major Roads
	Landfill		Local Roads
	Lava Flow		Background
	Marsh or swamp		Aerial Photography
	Mine or Quarry		
	Miscellaneous Water		
	Perennial Water		
	Rock Outcrop		
	Saline Spot		
	Sandy Spot		
	Severely Eroded Spot		
	Sinkhole		
	Slide or Slip		
	Sodic Spot		

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Hidalgo County, Texas
Survey Area Data: Version 19, Jun 11, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 20, 2015–Nov 5, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Custom Soil Resource Report

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
25	Hidalgo fine sandy loam, 0 to 1 percent slopes	1.5	59.5%
28	Hidalgo sandy clay loam, 0 to 1 percent slopes	0.0	1.4%
48	Racombes sandy clay loam, 0 to 1 percent slopes	1.0	39.1%
Totals for Area of Interest		2.6	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or

Custom Soil Resource Report

landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Custom Soil Resource Report

Hidalgo County, Texas

25—Hidalgo fine sandy loam, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2sxn
Elevation: 20 to 500 feet
Mean annual precipitation: 20 to 27 inches
Mean annual air temperature: 72 to 74 degrees F
Frost-free period: 300 to 365 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Hidalgo and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hidalgo

Setting

Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Calcareous loamy alluvium

Typical profile

Ap - 0 to 17 inches: fine sandy loam
Bk1 - 17 to 28 inches: sandy clay loam
Bk2 - 28 to 38 inches: clay loam
Ck - 38 to 80 inches: clay loam

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 35 percent
Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Sodium adsorption ratio, maximum: 10.0
Available water capacity: Moderate (about 7.8 inches)

Interpretive groups

Land capability classification (irrigated): 2s
Land capability classification (nonirrigated): 2s
Hydrologic Soil Group: B
Ecological site: R083DY019TX - Gray Sandy Loam
Hydric soil rating: No

Custom Soil Resource Report

Minor Components

Willacy

Percent of map unit: 10 percent

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Hydric soil rating: No

Brennan

Percent of map unit: 5 percent

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Ecological site: R083EY023TX - Sandy Loam

Hydric soil rating: No

28—Hidalgo sandy clay loam, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2sxxl

Elevation: 20 to 500 feet

Mean annual precipitation: 20 to 27 inches

Mean annual air temperature: 72 to 74 degrees F

Frost-free period: 300 to 365 days

Farmland classification: All areas are prime farmland

Map Unit Composition

Hidalgo and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hidalgo

Setting

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Calcareous loamy alluvium

Typical profile

Ap - 0 to 17 inches: sandy clay loam

Bk1 - 17 to 28 inches: sandy clay loam

Bk2 - 28 to 38 inches: clay loam

Ck - 38 to 80 inches: clay loam

Custom Soil Resource Report

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.57 to 1.98 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 35 percent
Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Sodium adsorption ratio, maximum: 10.0
Available water capacity: Moderate (about 7.8 inches)

Interpretive groups

Land capability classification (irrigated): 1
Land capability classification (nonirrigated): 2c
Hydrologic Soil Group: B
Ecological site: R083DY019TX - Gray Sandy Loam
Hydric soil rating: No

Minor Components

Raymondville

Percent of map unit: 7 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R083DY025TX - Clay Loam
Hydric soil rating: No

Racombes

Percent of map unit: 6 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: R083DY025TX - Clay Loam
Hydric soil rating: No

Willacy

Percent of map unit: 2 percent
Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Hydric soil rating: No

Custom Soil Resource Report

48—Racombes sandy clay loam, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2yndc
Elevation: 30 to 330 feet
Mean annual precipitation: 23 to 27 inches
Mean annual air temperature: 72 to 74 degrees F
Frost-free period: 280 to 365 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Racombes and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Racombes

Setting

Landform: Terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Calcareous loamy alluvium

Typical profile

Ap - 0 to 13 inches: sandy clay loam
Bt - 13 to 25 inches: sandy clay loam
Btk - 25 to 49 inches: sandy clay loam
Bk - 49 to 80 inches: sandy clay loam

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.57 to 1.98 in/hr)
Depth to water table: About 42 to 72 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 20 percent
Gypsum, maximum content: 2 percent
Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Sodium adsorption ratio, maximum: 6.0
Available water capacity: Moderate (about 9.0 inches)

Interpretive groups

Land capability classification (irrigated): 1
Land capability classification (nonirrigated): 1
Hydrologic Soil Group: B

Custom Soil Resource Report

Ecological site: R083DY025TX - Clay Loam

Hydric soil rating: No

Minor Components

Willacy

Percent of map unit: 6 percent

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Ecological site: R083DY023TX - Sandy Loam

Hydric soil rating: No

Raymondville

Percent of map unit: 4 percent

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Ecological site: R083DY025TX - Clay Loam

Hydric soil rating: No

Hidalgo

Percent of map unit: 4 percent

Landform: Terraces

Landform position (three-dimensional): Tread

Down-slope shape: Convex

Across-slope shape: Linear

Ecological site: R083DY019TX - Gray Sandy Loam

Hydric soil rating: No

Rio

Percent of map unit: 1 percent

Landform: Closed depressions

Landform position (three-dimensional): Tread

Down-slope shape: Concave

Across-slope shape: Concave

Ecological site: R083DY007TX - Lakebed

Hydric soil rating: Yes

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelpdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf



**Planning & Zoning Commission
Standardized Agenda Request Form**

Date of Meeting: February 3, 2021	Agenda Item No. (to be assigned by PCE): IV.C.
From: Rebekah de la Fuente, Planning Director, on behalf of Ezequiel Reyna Jr.	
Subject/Agenda Item: Discussion and consideration to convert South Border Avenue from a public street to a private street from the intersection of South Border Avenue and Tierra Santa Blvd. Weslaco, Hidalgo County, Texas. Possible Action.	
Discussion/Overview: The proposed conversion of South Border Avenue is being requested by the surrounding property owner. The owner has agreed to accept all required maintenance of the street. There is currently an existing gate at the intersection of Mile 5 North Road and Border Avenue as part of Tierra Santa Golf Club and Community.	
If item requires Publication Notice, provide date and periodical of publication; indicate if comments received from letters mailed to property owners: N/A	
Staff recommendation for Commission's Action: Staff recommends approval of the conversion to a private street	
Additional Action Prompted: ☒ Mayor's Signature ☐ Public Hearing ☐ Budget Amendment ☐ Resolution ☐ Ordinance – First Reading ☐ Ordinance – Final Reading	
Advisory Review, (if any): (name of board/committee, date of action, recommendation): N/A	
If item previously considered, provide date and action by Commission: N/A	
Attachments,(if any): Request letter.	
Responsibilities upon Commission's Action: Planning staff will advise applicant.	

Ezequiel Reyna Jr.
5000 S. Border
Weslaco, TX 78596

January 11, 2021


Mike Perez
City Manager
City of Weslaco
255 S. Kansas
Weslaco, TX 78596

Dear Mike Perez:

This letter is to request that the street that accesses my homestead be de-annexed by the City of Weslaco. The boundaries of this road are generally from the intersection of Border Avenue and Tierra Santa Boulevard; going south toward the IBWC floodway. I am the owner of the property located at 5000 S. Border, Weslaco, TX 78596 and all adjacent properties of the aforementioned portion of Border Avenue (referenced above). Seven years ago, my property was annexed by the City of Weslaco. As required by state law, within 2 ½ years of annexation, the City of Weslaco was required to provide "full municipal services" to my property. "Full municipal services" includes water, wastewater, roads and drainage as provided to all residences within city boundaries. I had previously notified the city that it had failed to provide any necessary services within the required timeframe. And while I am a proud tax paying member of my community, it is my belief that this annexation was done inappropriately and without the required and necessary planning. While I have remained patient, I have suffered damages to my vehicles and during the latest rain events, accessibility to my house has become increasingly difficult due to the unattended road improvements.

For these reasons, I am respectfully requesting for the city to de-annex the entire road referenced above (from "curb to curb") so that I may make the street improvements to the property myself. At your request, I will provide any necessary information for the de-annexation. I can be reached at 956-968-9556, as well.

Respectfully,



Ezequiel Reyna Jr.

Cc: Rebekah de la Fuente, City of Weslaco Planning Department